Construction Chemicals

SUBMITTAL DOCUMENT

TerraFloor C

Cement-Based Terrazzo
Decorative Floor System



Compressive
≥ 40 MPa

Durable
Abrasion & impact

UV Stable
Colour-fast

Fast Use
Walk-on 24 h

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 12

4. Approvals & Certificates 13

METHOD STATEMENT

TerraFloor C — Cement-Based Terrazzo Decorative Floor System

Project Name		**Document No.**	OMX-MS-TERRAFLOORC
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	TerraFloor C	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of TerraFloor C on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers surface preparation, priming, mixing, placing, finishing and curing of TerraFloor C cement-based terrazzo floor system on concrete substrates in industrial, commercial and public buildings.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Binder	Part A + Part B mixed together to bind the aggregates.
Aggregate	Part C engineered decorative aggregates.
Unit	Pre-weighed set of Part A, Part B and Part C.
Pot life	Time the mixed material remains workable.
Curing	Protecting the floor from rapid drying until it gains strength.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.

Role	Responsibility
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
TerraFloor C	Part A and Part B binder (30 kg pails), Part C aggregates (25 / 30 kg bags)
Primer	As recommended for the substrate
Joint materials	Divider strips and joint sealant where specified

5.1 Key product data

Property	Typical Value
Components	Binder Part A + Part B + aggregates Part C
Mixing ratio	Pre-weighed units — mix complete units as recommended
Layer thickness	4 – 10 mm
Compressive strength	≥ 40 MPa
Flexural strength	≥ 7 MPa
Bond strength	≥ 1.5 MPa
Heat resistance	up to 80 °C
Foot traffic	24 hours

6. Tools & Equipment

- Diamond grinder / shot blaster
- Industrial vacuum
- Forced-action or paddle mixer
- Trowels
- Squeegee
- Spiked roller
- Screed rails
- Moisture meter
- Thermo-hygrometer and surface thermometer (dew point check)

- Moisture meter
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Dust mask
- Knee pads
- Safety shoes

7. Storage & Handling

- 12 months in original, unopened packaging. Store dry at +5 °C to +35 °C; protect binder from frost and aggregates from moisture.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Protect bags from moisture; do not use material with lumps.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Check concrete strength (≥ 25 N/mm²) and moisture (< 5 %).
2. Diamond grind or shot blast to remove laitance and expose a sound surface.
3. Remove oil, grease and contaminants.
4. Repair cracks and holes; mark substrate joints.
5. Vacuum all dust and apply the primer.
6. Pre-wet absorbent surfaces to a saturated surface-dry condition; remove standing water.
7. Protect adjacent surfaces with masking tape and sheeting.
8. Obtain QA/QC approval of the prepared surface before starting the next step.

10. Mixing

1. Check the batch numbers of all three parts and record them.
2. Keep aggregates of one batch for each area.
3. Mix Part A and Part B together with a slow-speed mixer until uniform.
4. Add Part C aggregates gradually while mixing.
5. Mix to a uniform, lump-free consistency.
6. Mix complete units only.
7. Mix only the quantity that can be applied within the pot life.

11. Application

1. Install divider strips and screed rails where required.
2. Place the mixed material on the primed substrate while the primer is suitable for overcoating.
3. Spread with trowel, squeegee or roller to the specified thickness (4 – 10 mm).
4. Compact and finish the surface to a uniform texture.
5. Re-form joints in line with substrate joints.
6. Work in manageable areas and finish each area in one operation where possible.
7. Check layer thickness and consumption regularly and record the results.

12. Curing & Protection

- Protect from sun, wind, rain and traffic for 24 – 48 hours.
- Foot traffic after 24 hours; full service after 48 – 72 hours.
- Protect from sun, wind and rain; keep moist where required during the first 24 hours.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before priming	≥ 25 N/mm², moisture < 5 %, sound and clean	QA/QC
Climate	During work	+10 °C to +30 °C, RH ≤ 75 %	Site Engineer
Mixing	Each unit	Complete unit, uniform consistency	Site Engineer
Thickness	During application	4 – 10 mm as specified	QA/QC
Finish	After curing	Uniform colour and texture, no cracks	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry, packaging condition	Each delivery	Material inspection report

Activity	Inspection / Test	Frequency	Record
Climate	Air / substrate temperature, RH, dew point	Start of shift and every 4 hours	Daily climate log
Surface preparation	Visual, moisture, soundness	Each area	Inspection request (hold point)
Application	Consumption, thickness, appearance	Each coat / area	Daily progress report
Final inspection	Visual, continuity, finish	Each completed area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Colour variation	Mixed batches; inconsistent mixing	Use one batch per area; mix complete units
Cracking	Rapid drying; substrate cracks not treated	Protect during curing; respect substrate joints
Hollow areas	Poor preparation or primer	Remove, re-prepare and reapply
Uneven aggregate distribution	Insufficient mixing	Mix fully before placing

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles, overalls; eye-wash available
Inhalation of vapours / dust	Ventilation; masks as required
Slips and trips	Housekeeping; barricades and signs
Manual handling	Correct lifting technique; mechanical aids
Electrical tools	Inspected tools; protected cables

- Wear gloves, safety goggles and a dust mask when handling powders and aggregates.
- The binder contains cement and is alkaline when wet; avoid skin and eye contact.
- Use dust extraction during grinding.
- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools and mixers with water immediately after use.

17. Limitations

- Surface and ambient temperature: +10 °C to +30 °C.
- Relative humidity: max. 75 %.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate strength and moisture verified	☐ Yes ☐ No	
Surface ground and cleaned	☐ Yes ☐ No	
Primer applied	☐ Yes ☐ No	
Divider strips installed	☐ Yes ☐ No	
Complete units mixed	☐ Yes ☐ No	
Thickness verified	☐ Yes ☐ No	
Finish uniform	☐ Yes ☐ No	
Joints re-formed	☐ Yes ☐ No	
Cured and protected	☐ Yes ☐ No	
Area handed over	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

TerraFloor C — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Decorative Flooring

TerraFloor C

Cement-Based Terrazzo
Decorative Floor System



Product Description

TerraFloor C is a three-component, cement-based terrazzo flooring system consisting of a two-part binder (Part A and Part B) and engineered decorative aggregates (Part C). It produces a durable, seamless decorative floor that resists abrasion, impact, slipping and moisture, is UV stable, environmentally friendly and available in custom colours and textures.

Uses

- Factories and warehouses.
- Shops, offices and showrooms.
- Airports, malls and hospitals.
- Kitchens, basements and car parks.
- Decorative interior floors requiring a seamless finish.

Advantages

- Resistant to abrasion, impact and moisture.
- UV stable: colours do not fade.
- Custom colours, aggregates and textures.
- Slip resistant and easy to maintain.
- Fast installation: foot traffic after 24 hours.

Application

1. **Surface Preparation**
   Concrete ≥ 25 N/mm², moisture < 5 %; diamond grind or shot blast and remove oil; apply primer.
2. **Mixing**
   Mix binder Part A and Part B, then add the Part C aggregates and mix to a uniform consistency.
3. **Application**
   Spread with trowel, squeegee or roller to 4 – 10 mm, finish and cure for 24 – 48 hours.

Consumption

approx. 2.2 – 2.5 kg/m² per mm
binder : aggregate ≈ 2 : 3 by weight
E.g. approx. 13 – 15 kg/m² at 6 mm.

Packaging

Binder Part A and Part B in 30 kg pails; aggregates (Part C) in 25 kg or 30 kg bags.

Storage & Shelf Life

12 months in original, unopened packaging. Store dry at +5 °C to +35 °C; protect binder from frost and aggregates from moisture.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Components	Binder Part A + Part B + aggregates Part C	—
Mixing ratio	Pre-weighed units — mix complete units as recommended	—
Layer thickness	4 – 10 mm	—
Compressive strength	≥ 40 MPa	—
Flexural strength	≥ 7 MPa	—
Bond strength	≥ 1.5 MPa	—
Heat resistance	up to 80 °C	—
Foot traffic	24 hours	—
Full service	48 – 72 hours	—
Application temperature	+10 °C to +30 °C	—
Relative humidity	max. 75 %	—

Consumption

Thickness	Total (A + B + C)	Binder (A + B) / Aggregate (C)
4 mm	approx. 9 – 10 kg/m²	3.6 – 4 / 5.4 – 6 kg/m²
6 mm	approx. 13 – 15 kg/m²	5.2 – 6 / 7.8 – 9 kg/m²
10 mm	approx. 22 – 25 kg/m²	8.8 – 10 / 13.2 – 15 kg/m²

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Surface and ambient temperature: +10 °C to +30 °C.
- Relative humidity: max. 75 %.
- Substrate moisture: < 5 %.
- Concrete compressive strength: ≥ 25 N/mm².
- Protect from direct sun, wind and rain during application and early curing.

Application Notes

- Prime the prepared substrate before applying the terrazzo layer.
- Mix complete units only to keep colour and aggregate ratio consistent.
- Use one batch of aggregates per area to avoid colour variation.
- Form joints in line with substrate joints.
- Cure for 24 – 48 hours before light traffic; full service after 48 – 72 hours.

Health & Safety

- Wear gloves, safety goggles and a dust mask when handling powders and aggregates.
- The binder contains cement and is alkaline when wet; avoid skin and eye contact.
- Use dust extraction during grinding.

First Aid & Cleaning

- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.
- Inhalation of dust: move to fresh air.
- Ingestion: rinse mouth and seek medical advice.
- Clean tools and mixers with water immediately after use.

Construction Chemicals

Test Reports

TerraFloor C — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

TerraFloor C — Submittal Document

To be attached: approvals and certificates, where available.