Construction Chemicals

SUBMITTAL DOCUMENT

TerraFloor EP

Epoxy Terrazzo
Seamless Decorative Floor System



Compressive	Chemical	Hardness	Solvent-Free
65 N/mm²	Excellent resistance	Shore D 80	100 % solids

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 13

4. Approvals & Certificates 14

METHOD STATEMENT

TerraFloor EP — Epoxy Terrazzo Seamless Decorative Floor System

Project Name		**Document No.**	OMX-MS-TERRAFLOOREP
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	TerraFloor EP	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of TerraFloor EP on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers surface preparation, priming, mixing, screeding, grinding, grouting, polishing and sealing of TerraFloor EP epoxy terrazzo floor system.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Priming of the prepared surface.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Pot life	Time the mixed material remains workable after Part A and Part B are combined.
Recoat interval	Minimum and maximum time between coats to achieve inter-coat adhesion.
WFT / DFT	Wet film thickness measured during application / dry film thickness after cure.
Dew point	Temperature at which moisture condenses; the substrate must be at least 3 °C above it.
Kit / set	Pre-weighed Part A and Part B supplied to be mixed completely.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.

Role	Responsibility
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
TerraFloor EP	Epoxy binder Part A + Part B (pails) and filler Part C (30 kg bags)
Primer	O MIX epoxy primer
Grout	Pigmented epoxy grout for pore filling
Sealer	Sealing coat as specified
Divider strips	Brass, aluminium or plastic where specified

5.1 Key product data

Property	Typical Value
Components	Epoxy Part A + Part B + filler Part C
Mixing ratio	Pre-weighed units — mix complete units as recommended
Density (A + B + C)	approx. 2.5 kg/L
Solids content	100 %
Pot life	1 hour
Compressive strength	65 N/mm²
Flexural strength	25 N/mm²
Tensile strength	313 kg/cm²

6. Tools & Equipment

- Diamond grinder / shot blaster
- Industrial vacuum
- Pan (forced-action) mixer
- Screed rails
- Trowels
- Power float

- Terrazzo grinding machine with 50 / 100 / 200 grit stones
- Wet vacuum
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Wet-film thickness gauge
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Overalls
- Dust masks
- Ear protection
- Knee pads

7. Storage & Handling

- 12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep Part A and Part B of each kit together and do not mix parts from different batches.
- Store away from heat, sparks and ignition sources.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Check concrete age (≥ 28 days), soundness and moisture (< 4 %).
2. Diamond grind or shot blast to remove laitance and open the surface.
3. Repair cracks and holes; install divider strips where specified.
4. Vacuum all dust.

5. Apply O MIX epoxy primer at 0.2 – 0.3 kg/m² and broadcast sand if required.
6. Measure substrate temperature, air temperature and relative humidity; confirm the substrate is at least 3 °C above dew point.
7. Protect adjacent surfaces, drains and fixtures with masking tape and sheeting.
8. Obtain QA/QC approval of the prepared surface before starting the next step.

10. Mixing

1. Condition materials to between +15 °C and +25 °C before mixing.
2. Check the batch numbers and expiry dates of both parts and record them.
3. Mix Part A and Part B for 2 minutes until uniform.
4. Transfer to a pan (forced-action) mixer and add Part C filler.
5. Mix for 2 minutes to a uniform, workable mortar.
6. Mix complete units only.
7. Mix only the quantity that can be applied within the pot life.

11. Application

1. Place the mixed terrazzo on the primed surface between screed rails.
2. Spread and level to 10 mm thickness.
3. Compact and close the surface with a power float.
4. After 48 hours, grind off 1 – 2 mm with 50 grit stones and clean.
5. Apply grout to fill pores (0.1 – 0.3 kg/m²) and allow to cure.
6. Polish with 100 grit and then 200 grit stones.
7. Apply the sealing coat after cleaning and drying.
8. Work in manageable bays, keeping a wet edge to avoid lap marks.
9. Check consumption by area and wet film thickness regularly during application and record the results.

12. Curing & Protection

- Pot life 1 hour.
- Initial cure 24 hours; grinding after 48 hours; full cure 7 days.
- Protect from water, dust and traffic during curing.
- Protect the applied area from water, dust, other trades and traffic until the stated cure times are reached.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before priming	Sound, ≥ 28 days, moisture < 4 %	QA/QC
Climate	During work	+5 °C to +35 °C, RH ≤ 85 %, 3 °C above dew point	Site Engineer

Check	Stage	Acceptance Criteria	By
Thickness	During screeding	10 mm	QA/QC
Grinding	After 48 hours	1 – 2 mm removed, aggregate exposed evenly	QA/QC
Polish	Final	Uniform polish, pores filled, no defects	QA/QC + Consultant

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry, packaging condition	Each delivery	Material inspection report
Climate	Air / substrate temperature, RH, dew point	Start of shift and every 4 hours	Daily climate log
Surface preparation	Visual, moisture, soundness	Each area	Inspection request (hold point)
Application	Consumption, thickness, appearance	Each coat / area	Daily progress report
Final inspection	Visual, continuity, finish	Each completed area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Pinholes / bubbles	Outgassing from porous substrate; air entrapped in mixing	Seal with primer; mix at low speed; de-aerate with spiked roller; sand and recoat
Blushing / tacky surface	High humidity or low temperature during cure	Wash and abrade; recoat in suitable conditions
Poor adhesion	Contaminated, weak or damp substrate; recoat window exceeded	Remove, re-prepare surface and reapply
Soft spots	Incorrect mixing or ratio	Remove affected area and reapply with full kits
Uneven colour / lap marks	Loss of wet edge; different batches	Abrade and apply a further coat from one batch

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles, overalls; eye-wash available
Inhalation of vapours / dust	Ventilation; masks as required
Slips and trips	Housekeeping; barricades and signs
Manual handling	Correct lifting technique; mechanical aids
Electrical tools	Inspected tools; protected cables

- Wear chemical-resistant gloves, safety goggles and overalls.
- Uncured epoxy may cause skin sensitisation; avoid skin and eye contact.

- Use dust extraction and masks during grinding.
- Ensure good ventilation in enclosed areas.
- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: remove contaminated clothing and wash with soap and water; do not use solvents on skin.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools and mixers with epoxy thinner before the material cures.

17. Limitations

- Ambient and substrate temperature: +5 °C to +35 °C.
- Substrate moisture: < 4 %.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate verified	☐ Yes ☐ No	
Surface prepared	☐ Yes ☐ No	
Primer applied	☐ Yes ☐ No	
Divider strips installed	☐ Yes ☐ No	
Complete units mixed	☐ Yes ☐ No	
Screed 10 mm compacted	☐ Yes ☐ No	
Ground after 48 h	☐ Yes ☐ No	
Grout applied	☐ Yes ☐ No	
Polished 100 / 200 grit	☐ Yes ☐ No	
Sealer applied	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

TerraFloor EP — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Decorative Flooring

TerraFloor EP

Epoxy Terrazzo
Seamless Decorative Floor System



Product Description

TerraFloor EP is a solvent-free epoxy terrazzo floor system made of a pigmented epoxy binder (Part A + Part B) and a filler of decorative aggregates such as marble, stone or glass with marble powder (Part C). It is placed at 6 – 10 mm, then ground and polished to a seamless, decorative finish with excellent chemical and impact resistance.

Uses

- Restaurants and cafes.
- Car showrooms, hotels and malls.
- Hospitals and pharmaceutical plants.
- Airports and stations.
- Government and public buildings.
- Factories requiring decorative, hygienic floors.

Advantages

- Seamless, highly decorative finish.
- Excellent chemical resistance.
- High impact and abrasion resistance.
- Solvent-free, 100 % solids.
- Heat resistance up to 80 °C.

Application

1. **Primer**
   Apply O MIX epoxy primer at 0.2 – 0.3 kg/m² on the prepared substrate.
2. **Screed**
   Mix Parts A + B, add Part C in a pan mixer for 2 minutes; lay a 10 mm screed and power float.
3. **Grind & Polish**
   After 48 hours grind 1 – 2 mm (50 grit), grout, polish with 100 and 200 grit and apply the sealer.

Consumption

approx. 25 kg/m²
body layer at 10 mm (A + B + C)
Primer 0.2 – 0.3 kg/m²; grout layer 0.1 – 0.3 kg/m².

Packaging

Binder Part A and Part B in pails; filler Part C in 30 kg bags.

Storage & Shelf Life

12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Components	Epoxy Part A + Part B + filler Part C	—
Mixing ratio	Pre-weighed units — mix complete units as recommended	—
Density (A + B + C)	approx. 2.5 kg/L	—
Solids content	100 %	—
Pot life	1 hour	—
Compressive strength	65 N/mm²	—
Flexural strength	25 N/mm²	—
Tensile strength	313 kg/cm²	—
Hardness	Shore D approx. 80	—
Abrasion	0.07 g	—
Impact resistance	1.75 kg·m	—
Water absorption	approx. 0.05 %	—
Initial cure / full cure	24 hours / 7 days	—
Heat resistance	up to 80 °C	—

Consumption

Layer	Consumption
Primer	0.2 – 0.3 kg/m²
Terrazzo body (10 mm)	approx. 25 kg/m²
Grout layer	0.1 – 0.3 kg/m²
Sealing coat	As specified

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Ambient and substrate temperature: +5 °C to +35 °C.
- Substrate moisture: < 4 %.
- Substrate at least 3 °C above dew point.
- Concrete sound, at least 28 days old.
- Relative humidity: max. 85 %.

Application Notes

- Mix Part A + Part B first, then add Part C in a pan (forced-action) mixer for 2 minutes.
- Lay the screed at 10 mm and compact with a power float.
- Cure 48 hours before grinding.
- Grind 1 – 2 mm with 50 grit, fill pores with grout, then polish with 100 and 200 grit.
- Apply the sealing coat after polishing.

Health & Safety

- Wear chemical-resistant gloves, safety goggles and overalls.
- Uncured epoxy may cause skin sensitisation; avoid skin and eye contact.
- Use dust extraction and masks during grinding.
- Ensure good ventilation in enclosed areas.

First Aid & Cleaning

- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: remove contaminated clothing and wash with soap and water; do not use solvents on skin.
- Inhalation: move to fresh air; seek medical advice if symptoms persist.
- Ingestion: do not induce vomiting; seek medical advice immediately.
- Clean tools and mixers with epoxy thinner before the material cures.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

TerraFloor EP — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

TerraFloor EP — Submittal Document

To be attached: approvals and certificates, where available.