Construction Chemicals

SUBMITTAL DOCUMENT

Micromix Deco 1

Micro-Cement Base Coat
for Floors & Walls



Seamless
Floors & walls

Compressive
≥ 35 MPa

Adhesion
≥ 1.5 MPa

Renovation
Over tiles

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 12

4. Approvals & Certificates 13

METHOD STATEMENT

Micromix Deco 1 — Micro-Cement Base Coat for Floors & Walls

Project Name		**Document No.**	OMX-MS-MICROMIXDECO1
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Micromix Deco 1	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Micromix Deco 1 on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers surface preparation, priming, mixing and application of Micromix Deco 1 micro-cement base coat on floors, walls and stairs.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Pot life	Time the mixed material remains workable after adding water.
SSD	Saturated surface dry — substrate damp but without standing water.
Layer thickness	Thickness of one application pass.
Curing	Keeping the applied material protected from rapid drying until it gains strength.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.

Role	Responsibility
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
Micromix Deco 1	Micro-cement powder, 25 kg bags
Bondmix WB	Primer / bonding coat
Fiberlock	Reinforcement fabric where specified (Micromix HD floor systems)
Decora PU	Clear protective top coat

5.1 Key product data

Property	Typical Value
Form	Cementitious powder
Water / powder ratio	0.28 – 0.32
Layer thickness	1 – 2 mm
Working time	20 – 30 minutes
Drying time	approx. 3 hours
Next layer	after 24 hours
Adhesion	≥ 1.5 MPa
Flexural strength	≥ 7 MPa

6. Tools & Equipment

- Slow-speed mixer
- Buckets
- Stainless-steel trowels
- Flexible trowels
- Sanding machine (120 – 220 grit)
- Vacuum
- Measuring jugs
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter

- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Dust mask
- Knee pads

7. Storage & Handling

- 12 months in original, unopened bags. Store dry, off the ground, protected from moisture.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Protect bags from moisture; do not use material with lumps.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Check the substrate is sound, clean, dry and stable; remove loose tiles and contaminants.
2. Grind or sand glossy surfaces; fill holes and level defects.
3. Vacuum all dust.
4. Apply Bondmix WB primer at 0.2 kg/m² and allow to dry.
5. Protect adjacent surfaces with masking tape and sheeting.
6. Obtain QA/QC approval of the prepared and primed surface before application.

10. Mixing

1. Check the batch number and expiry date and record them.
2. Pour the measured clean water into the bucket.
3. Add the powder gradually while mixing at low speed.

4. Mix 3 minutes to a smooth, lump-free paste; rest 2 minutes and remix briefly.
5. Mix only the quantity that can be applied within the pot life.

11. Application

1. Apply the first layer with a steel trowel at 1 – 2 mm, embedding reinforcement where specified.
2. After 24 hours, lightly sand and remove dust.
3. Apply the second base layer if specified.
4. Proceed with Micromix Deco 2 finishing layers.
5. Work in manageable areas and finish each area in one operation where possible.
6. Check layer thickness and consumption regularly and record the results.

12. Curing & Protection

- Protect from rapid drying, sun and wind.
- Wait 24 hours between layers.
- Apply Decora PU after the final layer is dry and sanded.
- Protect from sun, wind and rain; keep moist where required during the first 24 hours.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before priming	Sound, clean, dry, stable	QA/QC
Mix	Each batch	W/P 0.28 – 0.32, lump-free	Site Engineer
Layer thickness	During application	1 – 2 mm	QA/QC
Surface	After 24 h	Even, no cracks or hollow areas	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry, packaging condition	Each delivery	Material inspection report
Climate	Air / substrate temperature, RH, dew point	Start of shift and every 4 hours	Daily climate log
Surface preparation	Visual, moisture, soundness	Each area	Inspection request (hold point)
Application	Consumption, thickness, appearance	Each coat / area	Daily progress report
Final inspection	Visual, continuity, finish	Each completed area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Shrinkage cracks	Rapid drying; layer too thick; excess water	Remove, reapply in thinner layers and protect from drying
Poor adhesion / hollow areas	Dusty or dry substrate	Remove, clean and pre-wet; reapply
Dusting surface	Excess water or late finishing	Light sanding and apply a fresh thin layer
Uneven finish	Insufficient trowelling	Sand and apply a finishing layer

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles, overalls; eye-wash available
Inhalation of vapours / dust	Ventilation; masks as required
Slips and trips	Housekeeping; barricades and signs
Manual handling	Correct lifting technique; mechanical aids
Electrical tools	Inspected tools; protected cables

- Wear gloves, safety goggles and a dust mask when mixing.
- Contains cement; alkaline when wet. Avoid skin and eye contact.
- Use dust extraction when sanding.
- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools with water immediately after use.

17. Limitations

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate sound, clean, dry and stable.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate sound and clean	☐ Yes ☐ No	
Primer applied	☐ Yes ☐ No	
Water ratio respected	☐ Yes ☐ No	
Reinforcement embedded (floors)	☐ Yes ☐ No	
Layer 1 – 2 mm	☐ Yes ☐ No	
24 h between layers	☐ Yes ☐ No	
Sanded and dust-free	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

Micromix Deco 1 — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Concrete Admixture



Micromix Deco 1

Micro-Cement Base Coat
for Floors & Walls

Product Description

Micromix Deco 1 is a cementitious micro-cement base coat for floors, walls and stairs. Applied in thin layers of 1 – 2 mm over concrete, screed, ceramic or terrazzo, it forms a strong, seamless base for Micromix Deco 2 finishing layers.

Uses

- Floors, walls and stairs.
- Bathrooms and kitchens.
- Showrooms and commercial interiors.
- Renovation over concrete, screed, ceramic tiles or terrazzo.

Advantages

- Seamless base coat, 1 – 2 mm per layer.
- Compressive strength ≥ 35 MPa.
- Adhesion ≥ 1.5 MPa.
- Applies over existing tiles and terrazzo.
- Base of the Micromix Deco system.

Application

1. **Surface Preparation**
   Sound, clean, stable substrate; prime with Bondmix WB.
2. **Mixing**
   Mix powder with water at a water/powder ratio of 0.28 – 0.32.
3. **Application**
   Apply 1 – 2 mm per layer with a steel trowel; next layer after 24 hours.

Consumption

1.6 – 1.8 kg/m² per mm
in 1 – 2 layers
Approx. 1 kg/m² per layer in the Micromix Deco systems.

Packaging

25 kg bags.

Storage & Shelf Life

12 months in original, unopened bags. Store dry, off the ground, protected from moisture.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Form	Cementitious powder	—
Water / powder ratio	0.28 – 0.32	—
Layer thickness	1 – 2 mm	—
Working time	20 – 30 minutes	—
Drying time	approx. 3 hours	—
Next layer	after 24 hours	—
Adhesion	≥ 1.5 MPa	—
Flexural strength	≥ 7 MPa	—
Compressive strength	≥ 35 MPa	—
Density	approx. 1.8 kg/L	—
Application temperature	+10 °C to +35 °C	—

Consumption

Layer	Consumption
Per mm of thickness	1.6 – 1.8 kg/m²
Base layer in Micromix Deco systems	approx. 1 kg/m²

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate sound, clean, dry and stable.
- Protect from direct sun, wind and rapid drying.
- Do not apply on substrates with rising damp.

Application Notes

- Water / powder ratio 0.28 – 0.32 (7.0 – 8.0 L per 25 kg bag).
- Embed Fiberlock reinforcement in the first layer on floors where specified.
- Lightly sand between layers.
- Finish with Micromix Deco 2 and protect with Decora PU.

Health & Safety

- Wear gloves, safety goggles and a dust mask when mixing.
- Contains cement; alkaline when wet. Avoid skin and eye contact.
- Use dust extraction when sanding.

First Aid & Cleaning

- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.
- Inhalation of dust: move to fresh air.
- Ingestion: rinse mouth and seek medical advice.
- Clean tools with water immediately after use.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

Micromix Deco 1 — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

Micromix Deco 1 — Submittal Document

To be attached: approvals and certificates, where available.