Construction Chemicals

SUBMITTAL DOCUMENT

Addmix SF

Cold-Drawn Steel Fibres
for Concrete Reinforcement



Tensile
Up to 1100 N/mm²

Toughness
Crack control

Types
Round, segmented, hooked

Mixing
Uniform spread

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 8

3. Test Reports 11

4. Approvals & Certificates 12

METHOD STATEMENT

Addmix SF — Cold-Drawn Steel Fibres for Concrete Reinforcement

Project Name		**Document No.**	OMX-MS-ADDMIXSF
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Addmix SF	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Addmix SF on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers dosing, mixing, placing and quality control of concrete containing Addmix SF.

- Approval of the mix design.
- Dosing at the batching plant or on site.
- Mixing and placing of concrete.
- Curing.
- Testing and documentation.

3. Definitions

Term	Meaning
Dosage	Quantity of Addmix SF per m³ of concrete or % of cement.
Mix design	Approved concrete proportions.
Slump	Measure of fresh concrete workability.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility and approvals.
Batching Plant Supervisor	Dosing, mixing and delivery records.
Site Engineer	Placing, compaction and curing.
QA/QC Inspector	Fresh and hardened concrete testing.

Role	Responsibility
HSE Officer	PPE and safe handling.
Storekeeper	Storage and batch control.

5. Materials

Material	Description
Addmix SF	20 kg and 25 kg cartons; 800 × 1200 pallets; approx. 25 t per 40 ft container.

5.1 Key product data

Property	Typical Value
Material	Cold-drawn wire, AISI 1010
Corrugated round	50 mm × 1.0 mm, L/D 50, 2800 pcs/kg, 1100 N/mm²
Corrugated segmented	50 mm, 2100 pcs/kg, 700 N/mm²
End-hooked	35 mm × 0.8 mm, L/D 43.75, 7200 pcs/kg, 1100 N/mm²

6. Tools & Equipment

- Calibrated scales or dispensers at the batching plant
- Concrete mixer / truck mixer
- Slump cone
- Cube moulds
- Slump cone, cube / cylinder moulds
- Curing compound or wet hessian

6.1 Personal protective equipment

- Gloves
- Goggles
- Dust mask
- Safety shoes

7. Storage & Handling

- Store dry and covered to prevent rusting.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep containers tightly closed and protect from frost and direct sunlight.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Mix design including dosage approved.
- Trial mix completed and approved.
- Dosing equipment calibrated.
- Team briefed.

9. Mix Design & Trial

1. Prepare trial mixes with the approved dosage (as per structural design).
2. Test workability, strength and other specified properties.
3. Approve the mix design.
4. Record the approved mix design.

10. Dosing

1. Check the batch number of the material and record it.
2. Weigh the fibre dosage per batch.

11. Mixing & Placing

1. Add fibres at about 20 – 40 kg per minute to the running mixer.
2. Mix at full speed for at least 5 minutes after the last fibre.
3. Place and finish.
4. Work in manageable areas and finish each area in one operation where possible.
5. Check layer thickness and consumption regularly and record the results.

12. Curing & Testing

- Cure as normal concrete.
- Protect from sun, wind and rain; keep moist where required during the first 24 hours.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before application	Prepared, sound and clean as specified	QA/QC
Climate	During work	Use the approved fibre type and dosage	Site Engineer
Consumption	During application	As per design per m^3 of concrete	QA/QC
Finish	After curing	Uniform, no defects	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, condition	Each delivery	Material inspection report
Dosing	Quantity per batch	Each batch	Batch ticket
Fresh concrete	Slump, temperature	Each truck	Delivery record
Hardened concrete	Compressive strength	As per specification	Test report

14. Defects & Remedies

Defect	Likely Cause	Remedy
Balling / clumping	Added too fast or at wrong stage	Add gradually with aggregates; extend mixing
Low workability	No dosage adjustment	Adjust superplasticiser in mix design
Plastic shrinkage cracks	Poor curing	Cure immediately

15. Health, Safety & Environment

Hazard	Control Measures
Dust / fibres	Dust mask, gloves, goggles
Machinery	Guards and trained operators
Manual handling	Correct lifting technique

- Wear gloves, safety goggles and a dust mask when mixing.
- Contains cement; alkaline when wet. Avoid skin and eye contact.
- Avoid inhaling dust.
- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean equipment with water.

17. Limitations

- Use only the approved dosage.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate prepared and approved	☐ Yes ☐ No	
Batch numbers recorded	☐ Yes ☐ No	
Material mixed as specified	☐ Yes ☐ No	
Applied at specified consumption	☐ Yes ☐ No	
Curing and protection carried out	☐ Yes ☐ No	
Final inspection passed	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

Addmix SF — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Accessories

Addmix SF

Cold-Drawn Steel Fibres
for Concrete Reinforcement



Product Description

Addmix SF is a range of cold-drawn steel fibres (AISI 1010) for reinforcing concrete. Available as corrugated round, corrugated segmented and end-hooked fibres, they improve crack control, toughness and impact resistance.

Uses

- Industrial floors and warehouses.
- Roads and pavements.
- Shotcrete.
- Precast elements.

Advantages

- High tensile strength up to 1100 N/mm².
- Improves toughness and crack control.
- Three fibre types.
- Uniform distribution.
- Reduces mesh installation time.

Application

1. **Mix Design**
   Set fibre type and dosage in the approved mix design.
2. **Dosing**
   Add fibres gradually with the aggregates or to the truck mixer.
3. **Mixing**
   Mix to uniform distribution, avoiding balling.

Consumption

As per design
per m³ of concrete
Dosage set by the structural design.

Packaging

20 kg and 25 kg cartons; 800 × 1200 pallets; approx. 25 t per 40 ft container.

Storage & Shelf Life

Store dry and covered to prevent rusting.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Material	Cold-drawn wire, AISI 1010	—
Corrugated round	50 mm × 1.0 mm, L/D 50, 2800 pcs/kg, 1100 N/mm²	—
Corrugated segmented	50 mm, 2100 pcs/kg, 700 N/mm²	—
End-hooked	35 mm × 0.8 mm, L/D 43.75, 7200 pcs/kg, 1100 N/mm²	—

Consumption

Type	Length	Tensile strength
Corrugated round	50 mm	1100 N/mm²
Corrugated segmented	50 mm	700 N/mm²
End-hooked	35 mm	1100 N/mm²

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Use the approved fibre type and dosage.
- Add gradually to avoid balling.

Application Notes

- Add fibres gradually to avoid balling.
- Use a superplasticiser to keep workability.
- Finish floors with power floats to bury fibres.

Health & Safety

- Wear gloves, safety goggles and a dust mask when mixing.
- Contains cement; alkaline when wet. Avoid skin and eye contact.
- Avoid inhaling dust.

First Aid & Cleaning

- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.
- Inhalation of dust: move to fresh air.
- Ingestion: rinse mouth and seek medical advice.
- Clean equipment with water.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

Addmix SF — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

Addmix SF — Submittal Document

To be attached: approvals and certificates, where available.