METHOD STATEMENT

Fiberlock — Woven Fiberglass Fabric ECR-Grade Glass Fibres

Project Name		**Document No.**	OMX-MS-FIBERLOCK
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Fiberlock	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Fiberlock on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers the preparation, cutting, installation and fixing of Fiberlock woven fiberglass fabric for thermal insulation, wrapping, welding protection and fire-protection uses.

- Inspection of the surfaces or items to be covered.
- Measuring and cutting the fabric.
- Installation with overlaps and fixings.
- Finishing and protection.
- Inspection and handover.

3. Definitions

Term	Meaning
ECR glass	Corrosion-resistant E-glass fibre.
Overlap	Width by which adjacent pieces cover each other.
Spiral wrap	Fabric wound around a pipe at an angle with overlap.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.

Role	Responsibility
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
Fiberlock	Woven fiberglass fabric, rolls 1 m × 50 m, thickness as specified
Fixings	Stainless-steel wire, pins, clips or high-temperature adhesive

5.1 Key product data

Property	Typical Value
Material	Woven ECR-glass fibre fabric
Colour	White
Temperature resistance	up to 550 °C
Thicknesses	0.125 / 0.175 / 0.4 / 0.8 / 1.5 / 3.0 mm
Roll size	1 m × 50 m
Properties	Thermal and electrical insulation; chemical resistant

6. Tools & Equipment

- Heavy-duty scissors
- Knives
- Tape measure
- Pliers
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Long sleeves
- Goggles

- Dust mask

7. Storage & Handling

- Store in original packaging in a dry place, away from moisture and mechanical damage.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Store rolls and cartons flat, off the ground, protected from direct sunlight, heat, oil and mechanical damage.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Check the surface or item is clean, dry and free of sharp edges.
2. Confirm the specified thickness and number of layers.
3. Measure and cut the fabric with allowance for overlaps.
4. Obtain QA/QC approval of surfaces before installation.

10. Cutting

1. Check the thickness and roll labels against the specification.
2. Cut on a clean table with sharp scissors or knives.
3. Seal or fold cut edges where fraying must be avoided.

11. Installation

1. Lay or wrap the fabric over the surface with the specified overlaps.
2. On pipes wrap spirally, overlapping each turn.
3. Secure with wire, pins, clips or adhesive at the specified spacing.
4. Install further layers where specified, staggering joints.
5. Record the area or length installed.

12. Finishing & Protection

- Apply the specified cladding, coating or jacket where required.
- Protect installed fabric from mechanical damage.
- Clean the work area of off-cuts and fibres.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Material	On receipt	Correct thickness and size	Storekeeper
Surface	Before installation	Clean, dry, no sharp edges	QA/QC
Overlaps / fixings	During installation	As specified	QA/QC
Final	After installation	Continuous, secure, undamaged	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Thickness, roll size, condition	Each delivery	Material inspection report
Installation	Overlaps, fixing, layers	Each area	Inspection request
Final	Continuity, no damage	Each area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Gaps at joints	Insufficient overlap	Add overlapping strip
Loose fabric	Fixings too far apart	Add fixings
Frayed edges	Blunt tools	Re-cut and seal edges

15. Health, Safety & Environment

Hazard	Control Measures
Cuts from knives and tools	Cut-resistant gloves
Fibres / dust irritation	Long sleeves, gloves, goggles, dust mask
Work at height	Approved access, harness where required
Manual handling of rolls	Correct lifting technique
Slips and trips	Housekeeping; barricades

- Glass fibres may irritate skin and eyes; wear gloves, long sleeves and safety goggles.
- Use a dust mask when cutting.

- Wash skin after handling.
- Eyes: rinse with clean water; do not rub.
- Skin: wash with cool water and soap.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Collect off-cuts and fibres with a vacuum.

17. Limitations

- Do not exceed the 550 °C temperature limit.
- Use the specified thickness for the exposure.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Thickness verified	☐ Yes ☐ No	
Surfaces clean and dry	☐ Yes ☐ No	
Fabric cut with overlaps	☐ Yes ☐ No	
Installed and fixed	☐ Yes ☐ No	
Joints staggered	☐ Yes ☐ No	
Finishing applied	☐ Yes ☐ No	
Area cleaned	☐ Yes ☐ No	

Inspected by	Signature	Date