METHOD STATEMENT

Bondmix SBR Plus — Hydrolysis-Resistant SBR Latex Mortar Modifier & Bonding Agent

Project Name		**Document No.**	OMX-MS-BONDMIXSBRPLUS
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Bondmix SBR Plus	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Bondmix SBR Plus on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers surface preparation, mixing and application of Bondmix SBR Plus as a bonding agent and mortar modifier for plasters, floor toppings, screeds, tile mortars and repair mortars.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Mortar modifier	Latex added to the gauging water to improve mortar properties.
Bonding coat	Latex / cement slurry brushed onto the substrate.
SSD	Saturated surface dry — damp substrate without standing water.
Wet-on-wet	Mortar placed while the bonding coat is still wet.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.

Role	Responsibility
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
Bondmix SBR Plus	SBR latex, 5 kg and 20 kg jerrycans
Cement and sand	As per mortar design

5.1 Key product data

Property	Typical Value
Base	Styrene-butadiene latex, hydrolysis resistant
Appearance	Milky white liquid
Density	1.0 – 1.1 kg/L
Solids content	45 – 50 %
Flammability	Non-flammable
Application temperature	+5 °C to +35 °C

6. Tools & Equipment

- Mixer
- Buckets
- Stiff brushes
- Trowels
- Screed rails
- Pressure washer
- Measuring jugs
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Dust mask
- Safety shoes

7. Storage & Handling

- 12 months in original, unopened packaging. Store at +5 °C to +35 °C; protect from frost and direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep containers tightly closed and protect from frost and direct sunlight.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Remove loose concrete, laitance, oil and contaminants.
2. Roughen smooth or low-absorbency surfaces mechanically.
3. Pre-wet the substrate to saturated surface dry; remove standing water.
4. Obtain QA/QC approval of the prepared surface before application.

10. Mixing

1. Check the batch number and expiry date and record them.
2. Shake or stir the container before use.
3. Mortar: add Bondmix SBR Plus to the gauging water as specified and reduce added water accordingly.
4. Bonding coat: dilute with water and mix with cement to a slurry — as recommended.
5. Mix to a uniform consistency without over-mixing.

11. Application

1. Brush the bonding coat into the damp substrate at 0.2 – 0.4 kg/m².
2. Place the modified mortar while the bonding coat is still wet.
3. Compact and finish as specified.
4. Record quantities used per area.

12. Curing & Protection

- Protect from rapid drying, sun and wind for at least 24 hours.
- Barricade the area until the mortar has set.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before application	Sound, clean, SSD	QA/QC
Dosage	Each batch	As specified	Site Engineer
Bonding coat	During application	Full coverage, wet when overlaid	Site Engineer
Bond	After curing	No hollow sound on tap test	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry	Each delivery	Material inspection report
Surface preparation	Clean, sound, SSD	Each area	Inspection request (hold point)
Mixing	Dosage and consistency	Each batch	Daily report
Final	Bond (tap test), finish	Each area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Debonding	Bonding coat dried; dusty substrate	Remove and reapply wet-on-wet
Cracking	Rapid drying; excess water	Reduce water; cure properly
Air bubbles	Over-mixing	Mix at low speed for the minimum time

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles; eye-wash available

Hazard	Control Measures
Cement dust	Dust masks when mixing slurries
Slips	Housekeeping; clean spills
Manual handling	Correct lifting technique

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- When mixed with cement the mix is alkaline.
- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools with water immediately after use.

17. Limitations

- Do not apply below +5 °C or on frozen substrates.
- Do not let the bonding coat dry before placing the mortar.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate prepared and SSD	☐ Yes ☐ No	
Dosage verified	☐ Yes ☐ No	
Bonding coat applied	☐ Yes ☐ No	
Mortar placed wet-on-wet	☐ Yes ☐ No	
Curing carried out	☐ Yes ☐ No	
Tap test passed	☐ Yes ☐ No	

Inspected by	Signature	Date