Construction Chemicals

SUBMITTAL DOCUMENT

# Bondmix SBR Plus

Hydrolysis-Resistant SBR Latex
Mortar Modifier & Bonding Agent




**Hydrolysis**
Resistant latex

**Abrasion**
Tougher surfaces

**Adhesion**
Bonding agent

**Salts**
Improved resistance

| | |
|---|---|
| **Project** | |
| **Main Contractor** | |
| **Consultant** | |
| **Submittal No. / Rev.** | 00 |
| **Date** | Nov 2026 |

Construction Chemicals

# Contents


1. Method Statement 3

2. Technical Data Sheet 8

3. Test Reports 11

4. Approvals & Certificates 12

METHOD STATEMENT

# Bondmix SBR Plus — Hydrolysis-Resistant SBR Latex Mortar Modifier & Bonding Agent

| | | | |
|---|---|---|---|
| **Project Name** | | **Document No.** | OMX-MS-BONDMIXSBRPLUS |
| **Main Contractor** | | **Revision** | 01 |
| **Consultant** | | **Date of Issue** | Nov 2026 |
| **Product** | Bondmix SBR Plus | **Status** | For Approval |

## 1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Bondmix SBR Plus on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

## 2. Scope of Work

This method statement covers surface preparation, mixing and application of Bondmix SBR Plus as a bonding agent and mortar modifier for plasters, floor toppings, screeds, tile mortars and repair mortars.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

## 3. Definitions

| Term | Meaning |
|---|---|
| **Mortar modifier** | Latex added to the gauging water to improve mortar properties. |
| **Bonding coat** | Latex / cement slurry brushed onto the substrate. |
| **SSD** | Saturated surface dry — damp substrate without standing water. |
| **Wet-on-wet** | Mortar placed while the bonding coat is still wet. |

## 4. Roles & Responsibilities

| Role | Responsibility |
|---|---|
| **Project Manager** | Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor. |
| **Site Engineer** | Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records. |

| Role | Responsibility |
|---|---|
| **QA/QC Inspector** | Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist. |
| **HSE Officer** | Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise. |
| **Foreman / Applicators** | Carry out the work as per this method statement and report any deviation immediately. |
| **Storekeeper** | Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers. |

## 5. Materials

| Material | Description |
|---|---|
| **Bondmix SBR Plus** | SBR latex, 5 kg and 20 kg jerrycans |
| **Cement and sand** | As per mortar design |

### 5.1 Key product data

| Property | Typical Value |
|---|---|
| **Base** | Styrene-butadiene latex, hydrolysis resistant |
| **Appearance** | Milky white liquid |
| **Density** | 1.0 – 1.1 kg/L |
| **Solids content** | 45 – 50 % |
| **Flammability** | Non-flammable |
| **Application temperature** | +5 °C to +35 °C |

## 6. Tools & Equipment

- Mixer
- Buckets
- Stiff brushes
- Trowels
- Screed rails
- Pressure washer
- Measuring jugs
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

### 6.1 Personal protective equipment

- Gloves
- Goggles
- Dust mask
- Safety shoes

## 7. Storage & Handling

- 12 months in original, unopened packaging. Store at +5 °C to +35 °C; protect from frost and direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep containers tightly closed and protect from frost and direct sunlight.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

## 8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

## 9. Surface Preparation

1. Remove loose concrete, laitance, oil and contaminants.
2. Roughen smooth or low-absorbency surfaces mechanically.
3. Pre-wet the substrate to saturated surface dry; remove standing water.
4. Obtain QA/QC approval of the prepared surface before application.

## 10. Mixing

1. Check the batch number and expiry date and record them.
2. Shake or stir the container before use.
3. Mortar: add Bondmix SBR Plus to the gauging water as specified and reduce added water accordingly.
4. Bonding coat: dilute with water and mix with cement to a slurry — as recommended.
5. Mix to a uniform consistency without over-mixing.

## 11. Application

1. Brush the bonding coat into the damp substrate at 0.2 – 0.4 kg/m².
2. Place the modified mortar while the bonding coat is still wet.
3. Compact and finish as specified.
4. Record quantities used per area.

## 12. Curing & Protection

- Protect from rapid drying, sun and wind for at least 24 hours.
- Barricade the area until the mortar has set.

## 13. Quality Control & Inspection

| Check | Stage | Acceptance Criteria | By |
|---|---|---|---|
| **Substrate** | Before application | Sound, clean, SSD | QA/QC |
| **Dosage** | Each batch | As specified | Site Engineer |
| **Bonding coat** | During application | Full coverage, wet when overlaid | Site Engineer |
| **Bond** | After curing | No hollow sound on tap test | QA/QC |

### 13.1 Inspection and test plan

| Activity | Inspection / Test | Frequency | Record |
|---|---|---|---|
| **Material receipt** | Product, batch, expiry | Each delivery | Material inspection report |
| **Surface preparation** | Clean, sound, SSD | Each area | Inspection request (hold point) |
| **Mixing** | Dosage and consistency | Each batch | Daily report |
| **Final** | Bond (tap test), finish | Each area | Handover checklist |

## 14. Defects & Remedies

| Defect | Likely Cause | Remedy |
|---|---|---|
| **Debonding** | Bonding coat dried; dusty substrate | Remove and reapply wet-on-wet |
| **Cracking** | Rapid drying; excess water | Reduce water; cure properly |
| **Air bubbles** | Over-mixing | Mix at low speed for the minimum time |

## 15. Health, Safety & Environment

| Hazard | Control Measures |
|---|---|
| **Skin and eye contact** | Gloves, goggles; eye-wash available |

| Hazard | Control Measures |
|---|---|
| **Cement dust** | Dust masks when mixing slurries |
| **Slips** | Housekeeping; clean spills |
| **Manual handling** | Correct lifting technique |

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- When mixed with cement the mix is alkaline.
- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.

### 15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

## 16. Cleaning

- Clean tools with water immediately after use.

## 17. Limitations

- Do not apply below +5 °C or on frozen substrates.
- Do not let the bonding coat dry before placing the mortar.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

## Appendix A — Inspection Checklist

| Inspection Item | Result | Remarks |
|---|---|---|
| **Substrate prepared and SSD** | ☐ Yes ☐ No | |
| **Dosage verified** | ☐ Yes ☐ No | |
| **Bonding coat applied** | ☐ Yes ☐ No | |
| **Mortar placed wet-on-wet** | ☐ Yes ☐ No | |
| **Curing carried out** | ☐ Yes ☐ No | |
| **Tap test passed** | ☐ Yes ☐ No | |

| Inspected by | Signature | Date |
|---|---|---|
| | | |

Construction Chemicals

# Technical Data Sheet

Bondmix SBR Plus — Submittal Document

Construction Chemicals

**Product Datasheet**
Edition: 01 | Date: Nov 2026
**Bonding Agents**

# Bondmix SBR Plus

Hydrolysis-Resistant SBR Latex
Mortar Modifier & Bonding Agent




## Product Description

Bondmix SBR Plus is a hydrolysis-resistant styrene-butadiene latex for modifying cement mortars and as a bonding agent. It reduces the water demand and improves workability, adhesion, abrasion resistance and resistance to salts, making it suitable for demanding plasters, floors and repairs.

## Uses

- High-abrasion plasters and floor toppings.
- Patching on low-absorbency surfaces.
- Polymer-modified repair mortars.
- Screeds and tile bedding mortars.
- Bonding agent for new mortars on old concrete.

## Advantages

- Hydrolysis resistant: suitable for wet conditions.
- Improves adhesion and flexibility.
- Increases abrasion resistance.
- Reduces water demand; better workability.
- Improves resistance to salts.

## Application

1. **Surface Preparation**
   Clean, sound substrate; pre-wet to saturated surface dry.
2. **Mixing**
   Add Bondmix SBR Plus to the gauging water of the mortar, or mix with cement to a bonding slurry — as recommended.
3. **Application**
   Apply the bonding coat and place the modified mortar while the coat is still wet.

## Consumption

**0.2 – 0.4 kg/m²**
as bonding agent (diluted)
As mortar modifier: dosage as specified for the mortar.

## Packaging

5 kg and 20 kg jerrycans.

## Storage & Shelf Life

12 months in original, unopened packaging. Store at +5 °C to +35 °C; protect from frost and direct sunlight.

## Technical Data

*Typical values at 25 °C*

| Property | Typical Value | Test Method |
|---|---|---|
| **Base** | Styrene-butadiene latex, hydrolysis resistant | — |
| **Appearance** | Milky white liquid | — |
| **Density** | 1.0 – 1.1 kg/L | — |
| **Solids content** | 45 – 50 % | — |
| **Flammability** | Non-flammable | — |
| **Application temperature** | +5 °C to +35 °C | — |

## Consumption

| Use | Consumption |
|---|---|
| **Bonding agent (diluted)** | 0.2 – 0.4 kg/m² |
| **Mortar modifier** | As specified for the mortar |

*Consumption is theoretical and varies with substrate porosity, profile and application method.*

## Application Conditions

- Application temperature: +5 °C to +35 °C.
- Substrate sound, clean, pre-wetted to saturated surface dry.
- Do not apply on frozen surfaces or in rain.
- Place the mortar while the bonding coat is still wet.

## Application Notes

- Replace part of the gauging water with Bondmix SBR Plus; reduce added water accordingly.
- For bonding coats, dilute with water and mix with cement to a slurry — as recommended.
- Do not over-mix modified mortars to avoid air entrainment.
- Cure modified mortars to avoid rapid drying.

## Health & Safety

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- When mixed with cement the mix is alkaline.

## First Aid & Cleaning

- Eyes: rinse immediately with plenty of clean water for at least 15 minutes and seek medical advice.
- Skin: wash with soap and water; cement is alkaline when wet.
- Inhalation of dust: move to fresh air.
- Clean tools with water immediately after use.

*The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.*

Construction Chemicals

# Test Reports

Bondmix SBR Plus — Submittal Document

*To be attached: laboratory test reports supporting the values in the Technical Data Sheet.*

Construction Chemicals

# Approvals & Certificates

Bondmix SBR Plus — Submittal Document

*To be attached: approvals and certificates, where available.*