Construction Chemicals

SUBMITTAL DOCUMENT

Acrycourt RAC

Acrylic Resurfacer
for Sport Courts



Levelling	Bond	Sand Mix	Water-Based
Fills pores	≥ 1.5 MPa	1 : 1 – 1 : 2	Low odour

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 12

4. Approvals & Certificates 13

METHOD STATEMENT

Acrycourt RAC — Acrylic Resurfacer for Sport Courts

Project Name		**Document No.**	OMX-MS-ACRYCOURTRAC
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Acrycourt RAC	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Acrycourt RAC on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers surface preparation, mixing and application of Acrycourt RAC acrylic resurfacer on asphalt and concrete sport courts.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Coat	One application pass of material over the full area.
Squeegee	Rubber blade used to spread acrylic court materials.
Recoat time	Minimum drying time before the next coat.
Acrylic court system	Primer, resurfacer, cushion layers and colour coats applied in sequence.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.

Role	Responsibility
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
Acrycourt RAC	20 kg pails and 200 kg drums.
Primer	Bondmix WB on concrete where specified
Silica sand	Clean, dry, graded, where specified

5.1 Key product data

Property	Typical Value
Base	Water-based acrylic
Colour	White
Density	1.30 – 1.40 kg/L
Solids content	50 – 60 %
Bond strength	≥ 1.5 MPa
Drying time	1 – 3 hours
Recoat time	6 – 12 hours
Sand addition	1 : 1 to 1 : 2 (product : sand) as recommended

6. Tools & Equipment

- Rubber squeegees
- Soft brooms
- Rollers
- Mixing drums
- Slow-speed mixer
- Line tape
- Blowers
- Straight edge
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter

- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Safety shoes

7. Storage & Handling

- 12 months in original, unopened packaging. Store at +5 °C to +35 °C; protect from frost and direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep containers tightly closed and protect from frost and direct sunlight.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Confirm asphalt age (≥ 14 days) or concrete age (≥ 28 days).
2. Clean the surface by pressure washing and blowing; remove oil, dust and loose material.
3. Repair cracks and depressions before resurfacing.
4. Prime concrete surfaces with Bondmix WB.
5. Check that ponding does not exceed the project tolerance (flood test) and correct low areas before coating.
6. Obtain QA/QC approval of the prepared surface before application.

10. Mixing

1. Check the batch numbers and colours and record them; use one batch per court where possible.
2. Stir Acrycourt RAC in its container.
3. Add silica sand at 1 : 1 to 1 : 2 (product : sand) and water as recommended.
4. Mix to a uniform squeegee consistency.

11. Application

1. Pour the mix in lines and spread with a rubber squeegee in one direction.
2. Apply 1 – 2 coats to a total of 1.0 – 2.0 kg/m².
3. Scrape ridges lightly between coats.
4. Work in straight passes in one direction; apply the next coat at 90° to the previous one.
5. Check consumption per coat and record it.

12. Curing & Protection

- Drying time 1 – 3 hours; recoat after 6 – 12 hours.
- Protect from rain, dew and traffic until dry.
- Do not open the court to play before the full cure time.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before application	Clean, dry, sound, repaired	QA/QC
Climate	During work	+10 °C to +35 °C, no rain	Site Engineer
Consumption	Each coat	1.0 – 2.0 kg/m² total	QA/QC
Finish	After drying	Uniform, pores filled, no ridges	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, colour, batch, expiry	Each delivery	Material inspection report
Substrate	Cure, planarity, cleanliness	Each court	Inspection request (hold point)
Climate	Temperature, rain forecast	Start of each shift	Daily log
Each coat	Consumption, uniformity	Each coat	Daily report
Final	Colour, texture, line marking	Each court	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Ridges / squeegee marks	Too thick or uneven passes	Scrape and apply a further thin coat
Cracking	Too thick; fast drying	Apply thinner coats; avoid hot hours
Poor adhesion	Dirty or damp surface	Clean, dry and reapply

15. Health, Safety & Environment

Hazard	Control Measures
Eye and skin contact	Gloves, goggles
Slips on wet coatings	Barricades and signs
Manual handling of pails and drums	Correct lifting technique
Heat stress (outdoor work)	Shade, water, work schedule

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- Ensure ventilation in enclosed areas.
- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools with water immediately after use.

17. Limitations

- Do not apply below +10 °C, above +35 °C surface temperature, or when rain is expected.
- Do not apply on asphalt younger than 14 days or concrete younger than 28 days.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate age verified	☐ Yes ☐ No	
Surface cleaned	☐ Yes ☐ No	
Cracks repaired	☐ Yes ☐ No	
Primer applied (concrete)	☐ Yes ☐ No	
Sand mix as recommended	☐ Yes ☐ No	
Coats applied crosswise	☐ Yes ☐ No	
Consumption recorded	☐ Yes ☐ No	
Finish uniform	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

Acrycourt RAC — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Sport Court Systems



Acrycourt RAC

Acrylic Resurfacer
for Sport Courts

Product Description

Acrycourt RAC is a water-based acrylic resurfacer and filler for asphalt and concrete sport courts. Mixed with silica sand and water, it fills pores and minor depressions and gives a uniform, levelled base for the cushion and colour coats.

Uses

- Tennis, basketball and multi-purpose courts.
- Resurfacing new or old asphalt and concrete.
- Filling pores and minor depressions.
- Base layer of the O MIX Hard and Soft Acrylic court systems.

Advantages

- Fills pores and levels the surface.
- Bond strength ≥ 1.5 MPa.
- Mixed with sand on site.
- Water-based, low odour.
- Uniform base for colour coats.

Application

1. **Surface Preparation**
   Clean, dry, sound asphalt or concrete; prime concrete with Bondmix WB.
2. **Mixing**
   Mix 1 part Acrycourt RAC with 1 – 2 parts silica sand and water as recommended.
3. **Application**
   Spread with a rubber squeegee; allow each coat to dry before the next.

Consumption

1.0 – 2.0 kg/m²
total, in 1 – 2 coats
1.5 kg/m² in the O MIX Hard / Soft Acrylic systems.

Packaging

20 kg pails and 200 kg drums.

Storage & Shelf Life

12 months in original, unopened packaging. Store at +5 °C to +35 °C; protect from frost and direct sunlight.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Base	Water-based acrylic	—
Colour	White	—
Density	1.30 – 1.40 kg/L	—
Solids content	50 – 60 %	—
Bond strength	≥ 1.5 MPa	—
Drying time	1 – 3 hours	—
Recoat time	6 – 12 hours	—
Sand addition	1 : 1 to 1 : 2 (product : sand) as recommended	—

Consumption

Use	Consumption
Resurfacing (1 – 2 coats)	1.0 – 2.0 kg/m²
Hard / Soft Acrylic systems	1.5 kg/m²

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Air and surface temperature: +10 °C to +35 °C.
- Do not apply when rain or dew is expected before the coat has dried.
- Asphalt at least 14 days old; concrete at least 28 days old.
- Surface clean, dry, sound and free of oil and loose material.

Application Notes

- Mix sand and water as recommended to a squeegee consistency.
- Apply in thin coats; do not fill depressions deeper than the layer thickness in one pass.
- Allow each coat to dry fully before the next.
- Lightly scrape ridges between coats.

Health & Safety

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- Ensure ventilation in enclosed areas.

First Aid & Cleaning

- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.
- Inhalation: move to fresh air.
- Clean tools with water immediately after use.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

Acrycourt RAC — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

Acrycourt RAC — Submittal Document

To be attached: approvals and certificates, where available.