METHOD STATEMENT

Mixflex SBR — Recycled SBR Rubber Granules Infill & Shock Pad

Project Name		**Document No.**	OMX-MS-MIXFLEXSBR
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Mixflex SBR	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Mixflex SBR on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers the spreading of Mixflex SBR rubber infill into artificial turf and the installation of bound SBR shock layers.

- Inspection of the turf or base.
- Spreading and brushing infill.
- Mixing and laying bound layers.
- Levelling and inspection.
- Handover.

3. Definitions

Term	Meaning
Infill	Granules brushed between turf fibres.
Shock pad	Resilient layer under a sports surface.
Bound layer	Granules mixed with PU binder and compacted.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.

Role	Responsibility
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
Mixflex SBR	Rubber granules, 25 kg bags, grade as specified
PU binder	For bound layers, as specified

5.1 Key product data

Property	Typical Value
Material	Recycled SBR rubber
Hardness	Shore A 70
Tensile strength	3 MPa
Elongation	180 %
Bulk density	0.78 g/cm³

6. Tools & Equipment

- Mechanical broom / top dresser
- Spreaders
- Forced-action mixer
- Screed rails
- Trowels
- Roller
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Dust mask

- Safety shoes

7. Storage & Handling

- Store dry and covered, away from heat sources.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Store rolls and cartons flat, off the ground, protected from direct sunlight, heat, oil and mechanical damage.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Confirm the turf is installed and seams are complete.
2. Confirm the base for bound layers is level and clean.
3. Check grain size against the specification.
4. Obtain QA/QC approval before spreading.

10. Preparation of Material

1. Check bag labels for grade.
2. Infill: use as supplied.
3. Bound layers: mix granules with PU binder in a forced-action mixer as specified.

11. Spreading / Laying

1. Spread infill in several thin passes.
2. Brush into the turf with a mechanical broom after each pass.
3. Check depth at several points.
4. Bound layers: lay between screed rails, level and compact.
5. Record quantities per area.

12. Finishing & Protection

- Allow bound layers to cure as per the binder datasheet.
- Protect from traffic until cured.
- Final brushing and inspection of infill.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Material	On receipt	Correct grade	Storekeeper
Infill depth	After spreading	As per design	QA/QC
Bound layer	After curing	Firm, level	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Grade, condition	Each delivery	Material inspection report
Infill	Depth, uniformity	Each area	Daily report
Bound layer	Thickness, level	Each area	Inspection request
Final	Uniform surface	Each area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Uneven infill	Single heavy pass	Spread in thin passes and brush
Loose bound layer	Low binder content	Remove and relay
Puddling	Uneven base	Correct base levels

15. Health, Safety & Environment

Hazard	Control Measures
Dust	Dust masks
Machinery	Trained operators
Manual handling of bags	Correct lifting technique
Heat stress	Shade, water

- Wear gloves and a dust mask during spreading.
- Keep away from heat and ignition sources.
- Avoid inhalation of fine dust.

- Eyes: rinse with clean water.
- Inhalation: move to fresh air.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Collect spills with a broom or vacuum.

17. Limitations

- Spread infill only when dry.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Grade verified	☐ Yes ☐ No	
Turf / base approved	☐ Yes ☐ No	
Infill spread in passes	☐ Yes ☐ No	
Brushed in	☐ Yes ☐ No	
Depth checked	☐ Yes ☐ No	
Bound layers cured	☐ Yes ☐ No	
Final inspection	☐ Yes ☐ No	

Inspected by	Signature	Date