Construction Chemicals

SUBMITTAL DOCUMENT

Roofguard PUR

Water-Based Acrylic-PU
Elastic UV-Resistant Waterproofing



Reflective
UV resistant

Elastic
≥ 200 %

Chlorides
96 % reduction

Low VOC
23 g/L

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 12

4. Approvals & Certificates 13

METHOD STATEMENT

Roofguard PUR — Water-Based Acrylic-PU Elastic UV-Resistant Waterproofing

Project Name		**Document No.**	OMX-MS-ROOFGUARDPUR
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	Roofguard PUR	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of Roofguard PUR on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers preparation, mixing, application, curing and inspection of Roofguard PUR (water-based acrylic-pu elastic uv-resistant waterproofing).

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Pot life	Time the mixed material remains workable after adding water.
SSD	Saturated surface dry — substrate damp but without standing water.
Layer thickness	Thickness of one application pass.
Curing	Keeping the applied material protected from rapid drying until it gains strength.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.

Role	Responsibility
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
Roofguard PUR	5 kg and 20 kg pails.

5.1 Key product data

Property	Typical Value
Finish / colours	Semi-gloss; white, grey
Solids content	55 %
DFT	100 – 1000 µm
Surface dry	1 – 2 hours
Recoat	from 6 hours (no maximum)
VOC	23 g/L
Hardness	Shore A 80
Tensile strength	4.2 N/mm²

6. Tools & Equipment

- Pressure washer
- Wire brushes
- Slow-speed mixer
- Brushes
- Rollers
- Airless spray
- Wet-film comb
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Overalls
- Mask for spray

7. Storage & Handling

- 12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep containers tightly closed and protect from frost and direct sunlight.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Remove dust, dirt, oil, efflorescence and loose material.
2. Repair cracks and defects.
3. Ensure the surface is sound and dry (or as specified).
4. Pre-wet absorbent surfaces to a saturated surface-dry condition; remove standing water.
5. Protect adjacent surfaces with masking tape and sheeting.
6. Obtain QA/QC approval of the prepared surface before starting the next step.

10. Mixing

1. Check the batch number and expiry date and record them.
2. Stir well before use.

11. Application

1. Apply the first coat by brush or roller.
2. Apply the second coat after 6 hours.

3. Apply extra coats at corners and joints.
4. Work in manageable areas and finish each area in one operation where possible.
5. Check layer thickness and consumption regularly and record the results.

12. Curing & Protection

- Surface dry 1 – 2 hours; protect from rain until dry.
- Protect from sun, wind and rain; keep moist where required during the first 24 hours.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before application	Prepared, sound and clean as specified	QA/QC
Climate	During work	Ambient and substrate temperature: +10 °C to +35 °C	Site Engineer
Consumption	During application	0.5 kg/m² at 500 µm (2 coats)	QA/QC
Finish	After curing	Uniform, no defects	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry, packaging condition	Each delivery	Material inspection report
Climate	Air / substrate temperature, RH, dew point	Start of shift and every 4 hours	Daily climate log
Surface preparation	Visual, moisture, soundness	Each area	Inspection request (hold point)
Application	Consumption, thickness, appearance	Each coat / area	Daily progress report
Final inspection	Visual, continuity, finish	Each completed area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Shrinkage cracks	Rapid drying; layer too thick; excess water	Remove, reapply in thinner layers and protect from drying
Poor adhesion / hollow areas	Dusty or dry substrate	Remove, clean and pre-wet; reapply
Dusting surface	Excess water or late finishing	Light sanding and apply a fresh thin layer
Uneven finish	Insufficient trowelling	Sand and apply a finishing layer

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles, overalls; eye-wash available
Inhalation of vapours / dust	Ventilation; masks as required
Slips and trips	Housekeeping; barricades and signs
Manual handling	Correct lifting technique; mechanical aids
Electrical tools	Inspected tools; protected cables

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- Ensure ventilation in enclosed areas; use a mask for spray application.
- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools with water immediately after use.

17. Limitations

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate prepared and approved	☐ Yes ☐ No	
Batch numbers recorded	☐ Yes ☐ No	
Material mixed as specified	☐ Yes ☐ No	
Applied at specified consumption	☐ Yes ☐ No	
Curing and protection carried out	☐ Yes ☐ No	
Final inspection passed	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

Roofguard PUR — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Waterproofing

Roofguard PUR

Water-Based Acrylic-PU
Elastic UV-Resistant Waterproofing



Product Description

Roofguard PUR is a water-based, elastic acrylic-polyurethane emulsion for waterproofing and protecting flat and pitched roofs, terraces, balconies, façades and ceilings. It is UV resistant, reflects sunlight and acts as a barrier against carbonation and chlorides. For pedestrian traffic only.

Uses

- Flat and pitched roofs.
- Terraces and balconies.
- Façades and ceilings.
- Anti-carbonation protection of concrete.

Advantages

- UV resistant and solar reflective.
- Elongation ≥ 200 %.
- Chloride reduction 96 %.
- Water-based, VOC 23 g/L.
- Up to 1 mm in one system.

Application

1. **Surface Preparation**
   Clean, sound substrate; form 45° coves; reinforce joints with O-Flex PVC.
2. **Mixing**
   Stir well before use.
3. **Application**
   Apply 2 coats for waterproofing (1 for anti-carbonation); extra coats at corners and joints.

Consumption

0.5 kg/m²
at 500 µm (2 coats)
One coat for anti-carbonation protection.

Packaging

5 kg and 20 kg pails.

Storage & Shelf Life

12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Finish / colours	Semi-gloss; white, grey	—
Solids content	55 %	—
DFT	100 – 1000 µm	—
Surface dry	1 – 2 hours	—
Recoat	from 6 hours (no maximum)	—
VOC	23 g/L	—
Hardness	Shore A 80	—
Tensile strength	4.2 N/mm²	—
Elongation	≥ 200 %	—
Adhesion	2 N/mm²	—
Water vapour transmission	43 g/m²/day	—
Chloride ion reduction	96 %	—

Consumption

Use	Coats	Consumption
Waterproofing	2	0.5 kg/m²
Anti-carbonation	1	approx. 0.25 kg/m²

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Relative humidity: max. 85 %.

Application Notes

- Apply 2 extra coats at corners and joints.
- Form 45° coves.
- Reinforce joints with O-Flex PVC.
- For pedestrian traffic only.

Health & Safety

- Wear gloves and safety goggles.
- Avoid contact with eyes and prolonged skin contact.
- Ensure ventilation in enclosed areas; use a mask for spray application.

First Aid & Cleaning

- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.
- Inhalation: move to fresh air.
- Ingestion: rinse mouth and seek medical advice.
- Clean tools with water immediately after use.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

Roofguard PUR — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

Roofguard PUR — Submittal Document

To be attached: approvals and certificates, where available.