Construction Chemicals

SUBMITTAL DOCUMENT

O-Poxy Plus

Solvent-Free Epoxy Floor Coating
for Heavy Traffic Areas



Solvent Free
100 % solids

Abrasion
64 – 67 mg loss

Heavy Traffic
40 – 47 N/mm²

Seamless
Easy to clean

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 13

4. Approvals & Certificates 14

METHOD STATEMENT

O-Poxy Plus — Solvent-Free Epoxy Floor Coating for Heavy Traffic Areas

Project Name		**Document No.**	OMX-MS-OPOXYPLUS
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	O-Poxy Plus	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of O-Poxy Plus on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers substrate preparation, priming, filling, mixing and application of O-Poxy Plus, a two-component epoxy floor coating, on concrete floors in industrial, commercial and parking areas.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Priming of the prepared surface.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Pot life	Time the mixed material remains workable after Part A and Part B are combined.
Recoat interval	Minimum and maximum time between coats to achieve inter-coat adhesion.
WFT / DFT	Wet film thickness measured during application / dry film thickness after cure.
Dew point	Temperature at which moisture condenses; the substrate must be at least 3 °C above it.
Kit / set	Pre-weighed Part A and Part B supplied to be mixed completely.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.

Role	Responsibility
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
O-Poxy Plus	Epoxy floor coating, 5 kg A + B sets
O-Prime SF	Solvent-free epoxy primer
O-Putty	Epoxy filler for defects
Quartz sand	0.1 – 0.4 mm, dry, for broadcast

5.1 Key product data

Property	Typical Value
Mixing ratio (A : B)	100 : 15 by weight
Solids content	100 %
Specific gravity	1.57
Colour	On request
Pot life (25 °C)	40 min
Recoat interval	24 hours
Hardening	12 – 24 hours
Full cure	7 days

6. Tools & Equipment

- Grinder / shot blaster
- Industrial vacuum
- Slow-speed mixer
- Notched spatula
- Rollers
- Spiked roller
- Moisture meter
- Wet-film gauge

- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Wet-film thickness gauge
- Measuring buckets and scale
- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Overalls
- Organic-vapour mask

7. Storage & Handling

- 12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep Part A and Part B of each kit together and do not mix parts from different batches.
- Store away from heat, sparks and ignition sources.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Check concrete age (≥ 28 days), strength (≥ 25 N/mm²) and moisture (< 4 %).
2. Grind or shot blast to remove laitance, oil, curing compounds and old coatings.
3. Vacuum all dust. Repair cracks and holes with O-Putty.
4. Measure substrate temperature, air temperature and relative humidity; confirm the substrate is at least 3 °C above dew point.
5. Protect adjacent surfaces, drains and fixtures with masking tape and sheeting.
6. Obtain QA/QC approval of the prepared surface before starting the next step.

10. Mixing

1. Condition materials to between +15 °C and +25 °C before mixing.
2. Check the batch numbers and expiry dates of both parts and record them.
3. Stir Part A to redistribute settled solids.
4. Add the full contents of Part B (ratio 100:15 by weight) and mix 2 – 3 minutes at low speed.
5. Mix complete sets only; do not thin.
6. Mix only the quantity that can be applied within the pot life.

11. Application

1. Apply O-Prime SF at 0.10 – 0.15 kg/m² and allow to cure.
2. Apply O-Putty where required and sand lightly.
3. Apply O-Poxy Plus at 0.25 – 0.30 kg/m² per coat with a notched spatula or roller, then de-aerate with a spiked roller.
4. Apply the next coat within 24 hours; if exceeded, abrade the surface first.
5. Work in manageable bays, keeping a wet edge to avoid lap marks.
6. Check consumption by area and wet film thickness regularly during application and record the results.

12. Curing & Protection

- Pot life 40 minutes at 25 °C.
- Hardening 12 – 24 hours; full cure 7 days.
- Protect from water, dirt and traffic during curing.
- Protect the applied area from water, dust, other trades and traffic until the stated cure times are reached.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before priming	≥ 28 days, ≥ 25 N/mm², moisture < 4 %	QA/QC
Climate	During work	+10 °C to +35 °C, RH ≤ 85 %, 3 °C above dew point	Site Engineer
Film thickness	During application	WFT checked with gauge per coat	QA/QC
Finished floor	After cure	Uniform colour, no pinholes, bubbles or soft spots	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry, packaging condition	Each delivery	Material inspection report

Activity	Inspection / Test	Frequency	Record
Climate	Air / substrate temperature, RH, dew point	Start of shift and every 4 hours	Daily climate log
Surface preparation	Visual, moisture, soundness	Each area	Inspection request (hold point)
Application	Consumption, thickness, appearance	Each coat / area	Daily progress report
Final inspection	Visual, continuity, finish	Each completed area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Pinholes / bubbles	Outgassing from porous substrate; air entrapped in mixing	Seal with primer; mix at low speed; de-aerate with spiked roller; sand and recoat
Blushing / tacky surface	High humidity or low temperature during cure	Wash and abrade; recoat in suitable conditions
Poor adhesion	Contaminated, weak or damp substrate; recoat window exceeded	Remove, re-prepare surface and reapply
Soft spots	Incorrect mixing or ratio	Remove affected area and reapply with full kits
Uneven colour / lap marks	Loss of wet edge; different batches	Abrade and apply a further coat from one batch

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles, overalls; eye-wash available
Inhalation of vapours / dust	Ventilation; masks as required
Slips and trips	Housekeeping; barricades and signs
Manual handling	Correct lifting technique; mechanical aids
Electrical tools	Inspected tools; protected cables

- Wear nitrile gloves, safety goggles and overalls.
- Uncured epoxy may cause skin sensitisation; avoid skin and eye contact.
- Ensure good ventilation in enclosed areas.
- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools with epoxy thinner before the material cures.

17. Limitations

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate age, strength and moisture verified	☐ Yes ☐ No	
Surface ground and vacuumed	☐ Yes ☐ No	
Primer applied and cured	☐ Yes ☐ No	
Defects filled with O-Putty	☐ Yes ☐ No	
Complete sets mixed (100:15)	☐ Yes ☐ No	
Climate conditions within limits	☐ Yes ☐ No	
Consumption / WFT per coat verified	☐ Yes ☐ No	
Recoat within 24 hours	☐ Yes ☐ No	
Final visual inspection passed	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

O-Poxy Plus — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Flooring

O-Poxy Plus

Solvent-Free Epoxy Floor Coating
for Heavy Traffic Areas



Product Description

O-Poxy Plus is a two-component, solvent-free epoxy floor coating for heavy traffic areas. It is applied on concrete, steel, non-ferrous metals and asbestos-cement surfaces and gives a hard-wearing, seamless and easy-to-clean finish.

Uses

- Heavy traffic industrial floors.
- Pharmaceutical and food facilities.
- Warehouses and logistics centres.
- Car parks, garages and ramps.
- Top coat in O MIX floor system MD.

Advantages

- Solvent-free, 100 % solids.
- Seamless, easy-to-clean finish.
- High abrasion resistance.
- High mechanical strength.
- Anti-slip option with additive.

Application

1. **Surface Preparation**
   Concrete ≥ 28 days, sound and dry (< 4 %). Grind or shot blast to remove laitance and contaminants.
2. **Priming**
   Prime with O-Prime SF at 0.10 – 0.15 kg/m². Fill defects with O-Putty.
3. **Application**
   Mix A + B for 2 – 3 min and spread with a notched trowel or roller.

Consumption

0.25 – 0.30 kg/m² per coat
approx. 160 – 190 µm film per coat (100 % solids)
Depends on substrate porosity and method.

Packaging

5 kg sets — pail + jerrycan: Part A 4.35 kg + Part B 0.65 kg.

Storage & Shelf Life

12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Mixing ratio (A : B)	100 : 15 by weight	—
Solids content	100 %	—
Specific gravity	1.57	ASTM D1475
Colour	On request	—
Pot life (25 °C)	40 min	—
Recoat interval	24 hours	—
Hardening	12 – 24 hours	—
Full cure	7 days	—
Compressive strength	40 – 47 N/mm²	ASTM D695
Flexural strength	20 – 27 N/mm²	ASTM D790
Tensile strength	20 – 25 N/mm²	ASTM D638
Bond strength to concrete	4.0 – 4.5 N/mm²	ASTM D4541
Abrasion resistance	64 – 67 mg loss	ASTM D4060
Film thickness per coat	approx. 160 – 190 µm (WFT = DFT, 100 % solids)	—

Consumption

Layer	Product	Consumption
Primer	O-Prime SF	0.10 – 0.15 kg/m²
Filling / levelling	O-Putty	0.25 – 0.30 kg/m²
Top coat	O-Poxy Plus	0.25 – 0.30 kg/m² per coat

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Relative humidity: max. 85 %.
- Substrate moisture content: < 4 %.
- Concrete at least 28 days old, ≥ 25 N/mm², pull-off ≥ 1.5 N/mm².

Application Notes

- Stir Part A, add all of Part B and mix for 2 – 3 minutes with a slow-speed mixer.
- Spread with a notched (American) spatula or roller; finish with a spiked roller.
- For a primer coat, broadcast quartz sand into the fresh material.
- For anti-slip finish, add anti-slip additive to the top coat.
- Do not apply on damp substrates or below +10 °C.

Health & Safety

- Wear nitrile gloves, safety goggles and overalls.
- Uncured epoxy may cause skin sensitisation; avoid skin and eye contact.
- Ensure good ventilation in enclosed areas.

First Aid & Cleaning

- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.
- Clean tools with epoxy thinner before the material cures.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

O-Poxy Plus — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

O-Poxy Plus — Submittal Document

To be attached: approvals and certificates, where available.