Construction Chemicals

SUBMITTAL DOCUMENT

# O-Prime SF

Solvent-Free Epoxy Primer
& Sealer for Concrete Floors




**Solvent Free**
100 % solids

**Penetrating**
Seals concrete

**Adhesion**
3 N/mm²

**Strength**
70 N/mm² compressive

| | |
|---|---|
| **Project** | |
| **Main Contractor** | |
| **Consultant** | |
| **Submittal No. / Rev.** | 00 |
| **Date** | Nov 2026 |

Construction Chemicals

# Contents


1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 12

4. Approvals & Certificates 13

METHOD STATEMENT

# O-Prime SF — Solvent-Free Epoxy Primer & Sealer for Concrete Floors

| | | | |
|---|---|---|---|
| **Project Name** | | **Document No.** | OMX-MS-OPRIMESF |
| **Main Contractor** | | **Revision** | 01 |
| **Consultant** | | **Date of Issue** | Nov 2026 |
| **Product** | O-Prime SF | **Status** | For Approval |

## 1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of O-Prime SF on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

## 2. Scope of Work

This method statement covers surface preparation, mixing and application of O-Prime SF, a solvent-free epoxy primer and sealer, on concrete floors before epoxy or polyurethane floor systems, and on steel and aluminium.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

## 3. Definitions

| Term | Meaning |
|---|---|
| **Pot life** | Time the mixed material remains workable after Part A and Part B are combined. |
| **Recoat interval** | Minimum and maximum time between coats to achieve inter-coat adhesion. |
| **WFT / DFT** | Wet film thickness measured during application / dry film thickness after cure. |
| **Dew point** | Temperature at which moisture condenses; the substrate must be at least 3 °C above it. |
| **Kit / set** | Pre-weighed Part A and Part B supplied to be mixed completely. |

## 4. Roles & Responsibilities

| Role | Responsibility |
|---|---|
| **Project Manager** | Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor. |

| Role | Responsibility |
|---|---|
| **Site Engineer** | Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records. |
| **QA/QC Inspector** | Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist. |
| **HSE Officer** | Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise. |
| **Foreman / Applicators** | Carry out the work as per this method statement and report any deviation immediately. |
| **Storekeeper** | Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers. |

## 5. Materials

| Material | Description |
|---|---|
| **O-Prime SF** | Solvent-free epoxy primer, 5 kg A + B sets |
| **Quartz sand** | 0.1 – 0.4 mm, dry |

### 5.1 Key product data

| Property | Typical Value |
|---|---|
| **Mixing ratio (A : B)** | As recommended — pre-weighed sets |
| **Solids content** | 100 % |
| **Specific gravity** | 1.06 |
| **Flash point** | 140 °C |
| **Pot life (25 °C)** | 40 min |
| **Recoat interval** | 10 hours (max. 24 hours) |
| **Foot traffic** | 24 hours |
| **Adhesion to concrete** | 3 N/mm² (concrete failure) |

## 6. Tools & Equipment

- Grinder / shot blaster
- Industrial vacuum
- Slow-speed mixer (< 300 rpm)
- Rollers
- Brushes
- Moisture meter
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Wet-film thickness gauge
- Measuring buckets and scale

- Masking tape and protective sheeting
- Lighting and extension cables

### 6.1 Personal protective equipment

- Gloves
- Goggles
- Overalls

## 7. Storage & Handling

- 12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep Part A and Part B of each kit together and do not mix parts from different batches.
- Store away from heat, sparks and ignition sources.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

## 8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

## 9. Surface Preparation

1. Check concrete age (≥ 28 days), strength (≥ 25 N/mm²) and moisture (< 4 %).
2. Grind or shot blast to an open, clean surface; remove laitance, oil and old coatings.
3. Vacuum all dust before priming.
4. Measure substrate temperature, air temperature and relative humidity; confirm the substrate is at least 3 °C above dew point.
5. Protect adjacent surfaces, drains and fixtures with masking tape and sheeting.
6. Obtain QA/QC approval of the prepared surface before starting the next step.

## 10. Mixing

1. Condition materials to between +15 °C and +25 °C before mixing.
2. Check the batch numbers and expiry dates of both parts and record them.
3. Pour all of Part B into Part A.

4. Mix 2 – 3 minutes below 300 rpm until uniform.
5. Mix complete sets only; do not thin.
6. Mix only the quantity that can be applied within the pot life.

## 11. Application

1. Apply by roller at 0.10 – 0.15 kg/m² without puddles.
2. Apply a second coat on very porous substrates.
3. Overcoat with the next system layer within 24 hours, or broadcast 0.1 – 0.4 mm quartz sand into the wet primer.
4. Work in manageable bays, keeping a wet edge to avoid lap marks.
5. Check consumption by area and wet film thickness regularly during application and record the results.

## 12. Curing & Protection

- Pot life 40 minutes at 25 °C.
- Recoat after 10 hours; foot traffic after 24 hours.
- Protect from moisture and dust until overcoated.
- Protect the applied area from water, dust, other trades and traffic until the stated cure times are reached.
- Barricade the area and display warning signs.

## 13. Quality Control & Inspection

| Check | Stage | Acceptance Criteria | By |
|---|---|---|---|
| **Substrate** | Before priming | ≥ 28 days, ≥ 25 N/mm², moisture < 4 % | QA/QC |
| **Climate** | During work | +10 °C to +35 °C, RH ≤ 85 %, 3 °C above dew point | Site Engineer |
| **Consumption** | During application | 0.10 – 0.15 kg/m² per coat | QA/QC |
| **Primed surface** | Before next layer | Uniform, no dry spots, overcoated within 24 h | QA/QC |

### 13.1 Inspection and test plan

| Activity | Inspection / Test | Frequency | Record |
|---|---|---|---|
| **Material receipt** | Product, batch, expiry, packaging condition | Each delivery | Material inspection report |
| **Climate** | Air / substrate temperature, RH, dew point | Start of shift and every 4 hours | Daily climate log |
| **Surface preparation** | Visual, moisture, soundness | Each area | Inspection request (hold point) |
| **Application** | Consumption, thickness, appearance | Each coat / area | Daily progress report |
| **Final inspection** | Visual, continuity, finish | Each completed area | Handover checklist |

## 14. Defects & Remedies

| Defect | Likely Cause | Remedy |
|---|---|---|
| **Pinholes / bubbles** | Outgassing from porous substrate; air entrapped in mixing | Seal with primer; mix at low speed; de-aerate with spiked roller; sand and recoat |
| **Blushing / tacky surface** | High humidity or low temperature during cure | Wash and abrade; recoat in suitable conditions |
| **Poor adhesion** | Contaminated, weak or damp substrate; recoat window exceeded | Remove, re-prepare surface and reapply |
| **Soft spots** | Incorrect mixing or ratio | Remove affected area and reapply with full kits |
| **Uneven colour / lap marks** | Loss of wet edge; different batches | Abrade and apply a further coat from one batch |

## 15. Health, Safety & Environment

| Hazard | Control Measures |
|---|---|
| **Skin and eye contact** | Gloves, goggles, overalls; eye-wash available |
| **Inhalation of vapours / dust** | Ventilation; masks as required |
| **Slips and trips** | Housekeeping; barricades and signs |
| **Manual handling** | Correct lifting technique; mechanical aids |
| **Electrical tools** | Inspected tools; protected cables |

- Wear nitrile gloves, safety goggles and overalls.
- Uncured epoxy may cause skin sensitisation; avoid skin and eye contact.
- Ensure good ventilation in enclosed areas.
- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.

### 15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

## 16. Cleaning

- Clean tools with epoxy thinner before the material cures.

## 17. Limitations

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

## Appendix A — Inspection Checklist

| Inspection Item | Result | Remarks |
|---|---|---|
| **Substrate age, strength and moisture verified** | ☐ Yes ☐ No | |
| **Surface ground and vacuumed** | ☐ Yes ☐ No | |
| **Complete sets mixed below 300 rpm** | ☐ Yes ☐ No | |
| **Climate conditions within limits** | ☐ Yes ☐ No | |
| **Consumption per coat verified** | ☐ Yes ☐ No | |
| **Second coat on porous areas** | ☐ Yes ☐ No | |
| **Overcoated within 24 hours or sand broadcast** | ☐ Yes ☐ No | |
| **Final visual inspection passed** | ☐ Yes ☐ No | |

| Inspected by | Signature | Date |
|---|---|---|
| | | |

Construction Chemicals

# Technical Data Sheet

O-Prime SF — Submittal Document

Construction Chemicals

**Product Datasheet**
Edition: 01 | Date: Nov 2026
**Flooring**

# O-Prime SF

Solvent-Free Epoxy Primer
& Sealer for Concrete Floors




## Product Description

O-Prime SF is a high-performance, two-component, solvent-free epoxy primer that penetrates and seals concrete surfaces. It is the base coat for O MIX epoxy and polyurethane floor systems and can also be applied on steel and aluminium.

## Uses

- Primer for epoxy and polyurethane floor systems.
- Sealing porous concrete and screeds.
- Dust-proofing of concrete floors.
- Primer on steel and aluminium substrates.
- Base coat in O MIX floor systems ST, MD, HD and HD Pro.

## Advantages

- Solvent-free, 100 % solids.
- Deep penetration, seals pores.
- Excellent adhesion: 3 N/mm².
- High mechanical strength.
- Flash point 140 °C.

## Application

1. **Surface Preparation**
   Concrete ≥ 28 days, dry (< 4 %). Grind or shot blast and vacuum all dust.
2. **Mixing**
   Add all of Part B to Part A and mix 2 – 3 min below 300 rpm.
3. **Application**
   Roll 0.10 – 0.15 kg/m². Overcoat within 24 h or broadcast sand.

## Consumption

**0.10 – 0.15 kg/m² per coat**
Two coats on very porous substrates
Depends on substrate porosity.

## Packaging

5 kg sets: Part A in pail + Part B in jerrycan.

## Storage & Shelf Life

12 months in original, unopened packaging. Store dry at +5 °C to +35 °C, away from direct sunlight.

## Technical Data

*Typical values at 25 °C*

| Property | Typical Value | Test Method |
|---|---|---|
| **Mixing ratio (A : B)** | As recommended — pre-weighed sets | — |
| **Solids content** | 100 % | — |
| **Specific gravity** | 1.06 | ASTM D1475 |
| **Flash point** | 140 °C | — |
| **Pot life (25 °C)** | 40 min | — |
| **Recoat interval** | 10 hours (max. 24 hours) | — |
| **Foot traffic** | 24 hours | — |
| **Adhesion to concrete** | 3 N/mm² (concrete failure) | ASTM D4541 |
| **Compressive strength** | 70 N/mm² | ASTM D695 |
| **Flexural strength** | 50 N/mm² | ASTM D790 |
| **Tensile strength** | 40 N/mm² | ASTM D638 |

## Consumption

| Substrate | Coats | Consumption |
|---|---|---|
| **Dense concrete** | 1 | 0.10 – 0.15 kg/m² |
| **Porous concrete / screed** | 2 | 0.10 – 0.15 kg/m² per coat |
| **Steel / aluminium** | 1 | 0.10 – 0.15 kg/m² |

*Consumption is theoretical and varies with substrate porosity, profile and application method.*

## Application Conditions

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Relative humidity: max. 85 %.
- Substrate moisture content: < 4 %.
- Concrete at least 28 days old, ≥ 25 N/mm², pull-off ≥ 1.5 N/mm².

## Application Notes

- Mix with a slow-speed mixer below 300 rpm to avoid air entrapment.
- Apply by roller or brush; do not leave puddles.
- Apply two coats on very porous substrates.
- Overcoat within 24 hours; otherwise broadcast 0.1 – 0.4 mm quartz sand into the wet primer.
- Do not thin.

## Health & Safety

- Wear nitrile gloves, safety goggles and overalls.
- Uncured epoxy may cause skin sensitisation; avoid skin and eye contact.
- Ensure good ventilation in enclosed areas.

## First Aid & Cleaning

- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.
- Clean tools with epoxy thinner before the material cures.

*The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.*

Construction Chemicals

# Test Reports

O-Prime SF — Submittal Document

*To be attached: laboratory test reports supporting the values in the Technical Data Sheet.*

Construction Chemicals

# Approvals & Certificates

O-Prime SF — Submittal Document

*To be attached: approvals and certificates, where available.*