Construction Chemicals

SUBMITTAL DOCUMENT

O-Putty

Two-Component Epoxy Filler
for Concrete, Steel & Equipment



Fast Drying
Overcoat after 24 h

Resistant
Heat & chemicals

Strength
60 N/mm² compressive

Versatile
Concrete, steel, equipment

Project	
Main Contractor	
Consultant	
Submittal No. / Rev.	00
Date	Nov 2026

Construction Chemicals

Contents

1. Method Statement 3

2. Technical Data Sheet 9

3. Test Reports 12

4. Approvals & Certificates 13

METHOD STATEMENT

O-Putty — Two-Component Epoxy Filler for Concrete, Steel & Equipment

Project Name		**Document No.**	OMX-MS-OPUTTY
Main Contractor		**Revision**	01
Consultant		**Date of Issue**	Nov 2026
Product	O-Putty	**Status**	For Approval

1. Purpose

This method statement defines the procedure, sequence, resources, quality checks and safety measures for the supply and application of O-Putty on site. It ensures that the work is carried out safely, in line with the approved drawings and project specification, and achieves the performance stated in the O MIX Technical Data Sheet.

2. Scope of Work

This method statement covers preparation, mixing and application of O-Putty, a two-component epoxy filler, for filling cracks, voids and defects in concrete floors, steel and equipment, and as the filling layer in O MIX floor systems.

- Inspection and acceptance of the substrate and the work area.
- Surface preparation and repair of defects.
- Priming of the prepared surface.
- Mixing and application of the material as described in this document.
- Curing, protection and handover of the completed area.
- Quality control, inspection and documentation of each stage.

3. Definitions

Term	Meaning
Pot life	Time the mixed material remains workable after Part A and Part B are combined.
Recoat interval	Minimum and maximum time between coats to achieve inter-coat adhesion.
WFT / DFT	Wet film thickness measured during application / dry film thickness after cure.
Dew point	Temperature at which moisture condenses; the substrate must be at least 3 °C above it.
Kit / set	Pre-weighed Part A and Part B supplied to be mixed completely.

4. Roles & Responsibilities

Role	Responsibility
Project Manager	Overall responsibility for planning, resources, approvals and coordination with the consultant and main contractor.

Role	Responsibility
Site Engineer	Supervises the work daily; confirms substrate readiness, climate conditions, mixing, consumption and sequence; keeps daily records.
QA/QC Inspector	Carries out inspections and tests at each stage, records results, raises inspection requests at hold points and signs the checklist.
HSE Officer	Conducts toolbox talks, checks PPE, ventilation, access and safe storage; stops work if unsafe conditions arise.
Foreman / Applicators	Carry out the work as per this method statement and report any deviation immediately.
Storekeeper	Receives, stores and issues materials in original packaging under the stated storage conditions; controls batch numbers.

5. Materials

Material	Description
O-Putty	Epoxy filler, 5 kg A + B sets

5.1 Key product data

Property	Typical Value
Mixing ratio (A : B)	1 : 1 by volume
Colour	White grey
Pot life (25 °C)	60 min
Drying time	24 hours
Full cure	7 days
Compressive strength	60 N/mm²
Flexural strength	30 N/mm²
Shelf life	12 months

6. Tools & Equipment

- Grinder
- Wire brush
- Vacuum
- Mixing board
- Steel spatula
- Trowel
- Sanding pad
- Thermo-hygrometer and surface thermometer (dew point check)
- Moisture meter
- Wet-film thickness gauge
- Measuring buckets and scale

- Masking tape and protective sheeting
- Lighting and extension cables

6.1 Personal protective equipment

- Gloves
- Goggles
- Overalls
- Organic-vapour mask

7. Storage & Handling

- 12 months in original, unopened packaging. Store dry and cool, away from heat and ignition sources.
- Store on pallets, off the ground, in a dry, covered and ventilated area.
- Keep containers closed until use; use materials on a first-in, first-out basis.
- Keep Part A and Part B of each kit together and do not mix parts from different batches.
- Store away from heat, sparks and ignition sources.
- Handle with care to avoid damage to packaging; do not stack beyond the safe height.

8. Pre-Start Requirements

- Material submittal, this method statement and the inspection plan approved by the consultant.
- Work area handed over clean, free of other trades and with safe access.
- Adequate lighting, power supply and ventilation available.
- Climate conditions checked and recorded before work starts.
- A trial area prepared and approved where required by the project.
- Toolbox talk held with the work team covering this method statement and the safety measures.

9. Surface Preparation

1. Substrate must be sound, clean and dry.
2. Open cracks with a grinder; remove dust, oil, rust and loose material.
3. Prime porous concrete with O-Prime SF where part of a floor system.
4. Measure substrate temperature, air temperature and relative humidity; confirm the substrate is at least 3 °C above dew point.
5. Protect adjacent surfaces, drains and fixtures with masking tape and sheeting.
6. Obtain QA/QC approval of the prepared surface before starting the next step.

10. Mixing

1. Condition materials to between +15 °C and +25 °C before mixing.
2. Check the batch numbers and expiry dates of both parts and record them.

3. Take equal volumes of Part A and Part B.
4. Mix on a clean board until uniform in colour, with no streaks.
5. Mix only the quantity that can be applied within the pot life.

11. Application

1. Press the filler firmly into cracks and voids with a steel spatula.
2. Skim the surface at 0.25 – 0.30 kg/m² where used as a filling layer.
3. After 24 hours, sand lightly and remove dust before overcoating.
4. Work in manageable bays, keeping a wet edge to avoid lap marks.
5. Check consumption by area and wet film thickness regularly during application and record the results.

12. Curing & Protection

- Pot life 60 minutes at 25 °C.
- Dry after 24 hours; full cure 7 days.
- Protect the applied area from water, dust, other trades and traffic until the stated cure times are reached.
- Barricade the area and display warning signs.

13. Quality Control & Inspection

Check	Stage	Acceptance Criteria	By
Substrate	Before filling	Sound, clean and dry	QA/QC
Mix	During work	Equal volumes, uniform colour	Site Engineer
Filled areas	After 24 h	Flush, hard, no shrinkage cracks	QA/QC
Surface	Before overcoat	Sanded and dust-free	QA/QC

13.1 Inspection and test plan

Activity	Inspection / Test	Frequency	Record
Material receipt	Product, batch, expiry, packaging condition	Each delivery	Material inspection report
Climate	Air / substrate temperature, RH, dew point	Start of shift and every 4 hours	Daily climate log
Surface preparation	Visual, moisture, soundness	Each area	Inspection request (hold point)
Application	Consumption, thickness, appearance	Each coat / area	Daily progress report
Final inspection	Visual, continuity, finish	Each completed area	Handover checklist

14. Defects & Remedies

Defect	Likely Cause	Remedy
Pinholes / bubbles	Outgassing from porous substrate; air entrapped in mixing	Seal with primer; mix at low speed; de-aerate with spiked roller; sand and recoat
Blushing / tacky surface	High humidity or low temperature during cure	Wash and abrade; recoat in suitable conditions
Poor adhesion	Contaminated, weak or damp substrate; recoat window exceeded	Remove, re-prepare surface and reapply
Soft spots	Incorrect mixing or ratio	Remove affected area and reapply with full kits
Uneven colour / lap marks	Loss of wet edge; different batches	Abrade and apply a further coat from one batch

15. Health, Safety & Environment

Hazard	Control Measures
Skin and eye contact	Gloves, goggles, overalls; eye-wash available
Fire (solvent vapours)	No smoking or hot work; fire extinguisher on site
Inhalation of vapours / dust	Ventilation; masks as required
Slips and trips	Housekeeping; barricades and signs
Manual handling	Correct lifting technique; mechanical aids
Electrical tools	Inspected tools; protected cables

- Contains solvent: keep away from sparks, flames and smoking.
- Wear gloves, goggles and overalls; use a mask in enclosed areas.
- Ensure good ventilation.
- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.

15.1 Waste & environment

- Collect empty containers and residues in designated bins.
- Do not discharge material or washings into drains or soil.
- Allow small quantities of leftover mixed material to cure before disposal; dispose of according to local regulations.

16. Cleaning

- Clean tools with epoxy thinner before the material cures.

17. Limitations

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Do not apply in rain or when rain is expected before the material has set.
- Any deviation from this method statement must be approved by the Site Engineer and the consultant.

Appendix A — Inspection Checklist

Inspection Item	Result	Remarks
Substrate sound, clean and dry	☐ Yes ☐ No	
Cracks opened and cleaned	☐ Yes ☐ No	
Equal volumes mixed to uniform colour	☐ Yes ☐ No	
Defects filled flush	☐ Yes ☐ No	
24 hours drying allowed	☐ Yes ☐ No	
Surface sanded and vacuumed	☐ Yes ☐ No	
Final visual inspection passed	☐ Yes ☐ No	

Inspected by	Signature	Date

Construction Chemicals

Technical Data Sheet

O-Putty — Submittal Document

Construction Chemicals

Product Datasheet
Edition: 01 | Date: Nov 2026
Flooring



O-Putty

Two-Component Epoxy Filler
for Concrete, Steel & Equipment

Product Description

O-Putty is a two-component, solvent-based epoxy filler for high-performance repairs. It fills cracks, voids and surface defects in concrete, steel and equipment, dries quickly and resists heat, chemicals and bacteria. Any epoxy coating can be applied over it after light sanding.

Uses

- Filling cracks and voids in concrete floors.
- Industrial, food and pharmaceutical floors.
- Garages, bridges and ramps.
- Repair of tanks, drums, pipes and equipment.
- Filling layer in O MIX floor systems.

Advantages

- Fast drying.
- Resistant to heat, chemicals and bacteria.
- High compressive strength: 60 N/mm².
- Excellent adhesion to concrete and steel.
- Can be overcoated with any epoxy.

Application

1. **Surface Preparation**
   Clean, dry and sound substrate. Remove dust, oil, rust and loose particles.
2. **Mixing**
   Mix Part A and Part B 1 : 1 by volume until uniform in colour.
3. **Application**
   Fill and level with a spatula or trowel. Sand lightly before coating.

Consumption

0.25 – 0.30 kg/m²
As a skim / filling layer
Higher on rough or damaged surfaces.

Packaging

5 kg sets (Part A + Part B), metal tins.

Storage & Shelf Life

12 months in original, unopened packaging.
Store dry and cool, away from heat and ignition sources.

Technical Data

Typical values at 25 °C

Property	Typical Value	Test Method
Mixing ratio (A : B)	1 : 1 by volume	—
Colour	White grey	—
Pot life (25 °C)	60 min	—
Drying time	24 hours	—
Full cure	7 days	—
Compressive strength	60 N/mm²	ASTM D695
Flexural strength	30 N/mm²	ASTM D790
Shelf life	12 months	—

Consumption

Use	Consumption
Skim / filling layer in floor systems	0.25 – 0.30 kg/m²
Crack and void filling	According to volume of defect

Consumption is theoretical and varies with substrate porosity, profile and application method.

Application Conditions

- Ambient and substrate temperature: +10 °C to +35 °C.
- Substrate at least 3 °C above dew point.
- Relative humidity: max. 85 %.
- Substrate moisture content: < 4 %.

Application Notes

- Mix equal volumes of Part A and Part B on a clean board until uniform.
- Apply with a steel spatula or trowel; press well into cracks.
- Allow 24 hours drying, then sand lightly before overcoating.
- Keep away from flames — contains solvent.

Health & Safety

- Contains solvent: keep away from sparks, flames and smoking.
- Wear gloves, goggles and overalls; use a mask in enclosed areas.
- Ensure good ventilation.

First Aid & Cleaning

- Eyes: rinse with clean water for 15 minutes and seek medical advice.
- Skin: wash with soap and water.
- Clean tools with epoxy thinner before the material cures.

The information in this datasheet is based on laboratory tests and practical experience and is given in good faith. Users should verify product suitability for their specific application. O MIX reserves the right to update this information without prior notice.

Construction Chemicals

Test Reports

O-Putty — Submittal Document

To be attached: laboratory test reports supporting the values in the Technical Data Sheet.

Construction Chemicals

Approvals & Certificates

O-Putty — Submittal Document

To be attached: approvals and certificates, where available.